

3"	BITUMINOUS CONCRETE PAVEMENT (1-1/4" TYPE III, 1-3/4" TYPE II)	406.25
3"	BASE COURSE, BITUMINOUS CONCRETE, TYPE I	406.25
30"	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35
18"	SAND BORROW (FROST PROTECTION)	203.31

20'-0" — 30'-0" MIN. CLEAR ZONE

SHOULDER VARIES 4'-0" TO 8'-0"

RAMP "C" VARIES 16'-0" TO 0'

TRAVELWAY 12'-0"

WB

TRAVELWAY 13'-0"

VARIES

SURVEY

TRAVELWAY 13'-0"

EB

TRAVELWAY 12'-0"

SHOULDER 8'-0"

30'-0" MIN. CLEAR ZONE

1'-0" OFFSET FOR STRIPING (TYP)

GRANITE SLOPE EDGING (SEE STD. SHT. C-1)

PGL

0.042 FT./FT.

0.042 FT./FT.

6" TYP

0.021 FT./FT.

1-1/4" SHOULDER PAVEMENT

3" SURFACE COURSE

3" BASE COURSE

30" SUBBASE

18" SAND BORROW

0.021 FT./FT. STRAIGHT

0.021 FT./FT. STRAIGHT

0.021 FT./FT. STRAIGHT

0.063 FT./FT.

2" TOPSOIL

VARIES

DITCH

4'-0"

1-4

1-3

1-2

1-4

FOR DITCH ELEVATIONS, SEE CROSS SECTIONS.

VT. 289 STA. 249+98.57 TO 251+00.00

255 + 39.64



-

THIS SHEET TO BE USED
FOR R.O.W. INFORMATION
ONLY.

SURVEYED BY VT SURVEY CONSULTANTS DATE FEB. 1988
 DRAWN BY BRYANT ASSOC. DATE _____
 TRACED BY _____ DATE _____

 COLCHESTER
 SECTION 4
 PROJ. 1R NO. 089-3(11)
 SHEET 3 OF 17