STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #6

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
304+63 LT	← ROYALTON 3	1	72	12	6.00						2					X		X															DI-1		E-123
	← VT LAW SCHOOL	1	72	12	6.00																												DI-1		E-123
	BETHEL 3 →	1	72	12	6.00											15.5 17.58																	DI-1		E-123
	RUTLAND 35 →	1	72	12	6.00																												DI-1		E-123
306+48 LT	EAST	1	24	12	2.00						2					X		X															M3-2		E-136B
	WEST	1	24	12	2.00											14.4																#2	M3-4		
	VERMONT 107	1	30	24	5.00											16.2																	MI-5		E-136B
	VERMONT 107	1	30	24	5.00																												MI-5		E-123
	⇦	1	21	15	2.19																												M6-1		E-136B
	⇨	1	21	15	2.19																												M6-1		
308+16 LT 308+16 RT	LT RT	2	36	36	18.00						4					15.25 15.5 X 15.2 15.7		X															W3-1A		E-150
313+08 RT		1	18	18	2.25						1				X 9.75			X															OMI-1		E-150
	SHEET 23			144.5	~~141.50~~	0	0								0	270	305.41			0			0	0				0	0	0					
	SHEET 24				128.38	0	0								0	240	235			0			0	0				0	0	0					
	SHEET 25			183.5	~~165.50~~	0	0								0 ~~15~~	420	427.15			~~42~~ 44.85			2	~~182~~ 216.50				0	0	0					
	SHEET 26				122.75	144.00	2								0	45	49.50			0			0	0				2	2	~~2310~~ 2295					
	SHEET 27				124.25	0	0								0	210	204.16			0			0	0				0	0	0					
	SHEET 28				62.63	0	0								0 ~~15~~	120	135.08			0			0	0				0	0	0					
															ROUNDING		1.24																		
																	357.55 LF																		
	ROUNDING				4.99	0	0								0	0				~~3~~			~~0~~	~~3~~				~~0~~	~~0~~	~~10~~					
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
															~~30~~ 0	1305				~~45~~ 44.85					~~185~~ 216.50											
	PROJECT TOTALS				SF 750.0	SF 144.00	EA. 2	SF				FT			FT ~~1335~~ 1357.55					LB ~~45~~ 44.85			EA. 2	LB ~~185~~ 216.50				EA. 2	EA. 2	LB ~~2320~~ 2295					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY, AND PAVEMENT MANAGEMENT SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #6

PROJECT NAME: ROYALTON-BETHEL
PROJECT NUMBER: IM 089-1(54)

FILE NAME: p06a198.dgn
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: p06a198tss6.i

PLOT DATE: 28-JUN-2010 15:12
DRAWN BY: MRS
CHECKED BY: PTS
SHEET 28 OF 37