

ITEM DETAIL SUMMARY SHEET 8

LOCATION			MISCELLANEOUS																REMARKS		
BEGIN MILE MARKER	END MILE MARKER	POS.	616.47	618.10	618.30	619.17	620.75	649.31	653.20	676.10			676.12								
			BIT. CONC. GUTTERS & TRAFF. ISL. TON	PORT. CEM. CONC. SIDEWALK, 5 INCH SY	DET. WARNING SURFACE SF	YEILDING MARKER POSTS EACH	SNOW BARRIER, GALV. LF	GEOTEXTILE UNDER STONE FILL SY	TEMP. EROSION MATTING SY	DELINEATOR W/STEEL POST			REMOVAL OF EXIST. DELINEATOR EACH								
										TYPE I EACH	TYPE II EACH	TYPE III EACH									
SOUTHBOUND EXIT 27 RAMP D																					
0.000	0.219	RT						7												RETAIN GUARDRAIL FROM MM 0.000 TO MM 0.219.REPAIR SLOPE EROSION AT MM 0.097, RT	
0.018	0.211									16	9		25								
0.055	0.143	LT																		REPAIR CABLE GUARDRAIL AS DIRECTED BY ENGINEER	
EXIT 28 RAMP A																					
0.012	0.199					1				23	9		32								
EXIT 28 RAMP B																					
0.000	0.276					2				9	6	8	23								
0.263	0.267	LT																			
EXIT 28 RAMP C																					
0.009	0.208					7				34	9		43								
0.117	0.122	LT	5.3																	CONSTRUCT BITUMINOUS CONCRETE GUTTER - SEE THE MISCELLANEOUS DETAIL SHEET	
0.149		RT	1.1																	CONSTRUCT BITUMINOUS CONCRETE GUTTER - SEE THE MISCELLANEOUS DETAIL SHEET	
0.208		RT	0.4																	CONSTRUCT BITUMINOUS CONCRETE GUTTER - SEE THE MISCELLANEOUS DETAIL SHEET	
EXIT 28 RAMP D																					
0.000	0.170					3				8	6	9	23								
0.103	0.186	RT																		RETAIN GUARDRAIL FROM MM 0.103 TO MM 0.186.	
EXIT 29 RAMP A																					
0.000	0.232					3				13	4	4	21								
EXIT 29 RAMP B																					
0.012	0.123									8	19	4	31								
EXIT 29 RAMP C																					
0.000	0.032									15		4	19								
EXIT 29 RAMP D																					
0.000	0.028									10		4	14								
WELCOME CENTER																					
0.000	0.360																				
7+56	17+31	LT																		RETAIN GUARDRAIL FROM STA. 7+56 TO STA. 17+31, LT.	
9+46		RT		10.6	12															CONSTRUCT SIDEWALK RAMP, TYPE 6	
10+04		RT		11.6	12															CONSTRUCT SIDEWALK RAMP, TYPE 6	
SHEET 2 SUBTOTALS:						155	76	365	300	293			293								
SHEET 4 SUBTOTALS:			20.8			141	73	117	325	288			274								
SHEET 6 SUBTOTALS:			5.3			7	152	7	325	89	23	20	132								
SHEET 8 SUBTOTALS:			6.8	22.2	24	16		7		136	62	33	231							* THESE TOTALS ARE CARRIED FORWARD TO THE DETAILED SUMMARY OF QUANTITIES ON THE QUANTITY SHEETS	
SUBTOTALS:			32.9	22.2	24	319	301	496	950	806	85	53	930							ITEM DETAIL SUMMARY SHEET #8	
ROUNDING:			2.1	2.8	2	6	9	-	-	9	5	7	10								
TOTALS:			35	25	26	325	310	496 *	950 *	815	90	60	940								
																				PROJECT NAME: DERBY PROJECT NUMBER: IM 091-3(46) FILE NAME: p06a200.dgn PROJECT LEADER: JLL DESIGNED BY: STANTEC IPARM FILE: p06a200ids08.i PLOT DATE: 07-SEP-2011 10:23 DRAWN BY: STANTEC CHECKED BY: JLL SHEET 16 OF 63	