QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
15000		15000	LF	SHOULDER BERM REMOVAL	203.40	EST
11700		11700	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	153
1		1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
10000		10000	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD	417.20	EST
360		360	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	11
100		100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COURSE AGGREGATE	580.20	EST
25		25	HR	POWER GRADER RENTAL	608.15	EST
200		200	HR	POWER BROOM RENTAL, TYPE 1	608.30	EST
600		600	HR	UNIFORMED TRAFFIC OFFICERS	630.10	-
400		400	HR	FLAGGERS	630.15	-
	1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
1		1	LS	TRAFFIC CONTROL	641.10	-
4		4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
153400		153400	LF	6 INCH WHITE LINE	646.214	1653
123400		123400	LF	6 INCH YELLOW LINE	646.215	1353
2450		2450	LF	12 INCH WHITE LINE	646.24	50
50		50	LF	24 INCH STOP BAR	646.26	4
48		48	EA	LETTER OR SYMBOL	646.30	-
76700		76700	LF	TEMPORARY 6 INCH WHITE LINE	646.620	827
61700		61700	LF	TEMPORARY 6 INCH YELLOW LINE	646.630	677
1225		1225	LF	TEMPORARY 12 INCH WHITE LINE	646.660	25
25		25	LF	TEMPORARY 24 INCH STOP BAR	646.680	2
24		24	EA	TEMPORARY LETTER OR SYMBOL	646.690	-
5000		5000	EA	LINE STRIPING TARGETS	646.76	1509
71300		71300	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	730
1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
192000		192000	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	2656
20		20	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE 1)	900.680	EST

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING-BIT. PAVEMENT
150	SY	BEGIN PROJECT
150	SY	END PROJECT
900	SY	BRIDGE 25S
1125	SY	BRIDGE 26S
450	SY	BRIDGE 27S
900	SY	BRIDGE 28S
600	SY	BRIDGE 29S
278	SY	U-TURN 35.675
278	SY	U-TURN 37.875
278	SY	U-TURN 39.420
278	SY	U-TURN 41.325
278	SY	U-TURN 43.185
278	SY	U-TURN 45.170
1711	SY	EXIT 7 OFF RAMP
133	SY	EXIT 7 OFF RAMP B
133	SY	EXIT 7 OFF RAMP F
367	SY	EXIT 7 ON RAMP
133	SY	EXIT 7 ON RAMP A
133	SY	EXIT 7 ON RAMP E
1283	SY	PARKING AREA OFF RAMP
1711	SY	PARKING AREA ON RAMP
11547	SY	SUBTOTAL
153	SY	ROUNDING
11700	SY	TOTAL
		PAVER-PLACED SURFACE TREATMENT, TYPE C
174715	SY	MAINLINE
278	SY	U-TURN 35.675
278	SY	U-TURN 37.875
278	SY	U-TURN 39.420
278	SY	U-TURN 41.325
278	SY	U-TURN 43.185
278	SY	U-TURN 45.170
1867	SY	EXIT 7 OFF RAMP
3427	SY	EXIT 7 OFF RAMP B
320	SY	EXIT 7 OFF RAMP F
400	SY	EXIT 7 ON RAMP
2827	SY	EXIT 7 ON RAMP A
853	SY	EXIT 7 ON RAMP E
1400	SY	PARKING AREA OFF RAMP
1867	SY	PARKING AREA ON RAMP
189344	SY	SUBTOTAL
2656	SY	ROUNDING
192000	SY	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: ROCKINGHAM - SPRINGFIELD
PROJECT NUMBER: IM SURF (10)

FILE NAME: ...08A150\...08A150.dgn
PROJECT LEADER: DOMEY
DESIGNED BY: HUNT
IPARM FILE NAME: 08A150_05.I

PLOT DATE: 02-AUG-2010 14:4
DRAWN BY: HUNT
CHECKED BY: PAVT MGMT
SHEET 5 OF 12