

STATE OF VERMONT AGENCY OF TRANSPORTATION											QUANTITY SHEET 1								
SUMMARY OF ESTIMATED QUANTITIES											TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
	ROADWAY	I91 - BRIDGE NO. 33S	I91 - BRIDGE NO. 34S	I91 - BRIDGE NO. 35N	I91 - BRIDGE NO. 35S	I91 - BRIDGE NO. 39N	I91 - BRIDGE NO. 39S	I91 - BRIDGE NO. 40S	FULL C.E. ITEMS		GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
	1										1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
		437	309	163	173	662	1119	1235			4098		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
		5	2	2	2	3	4	5			23		CWT	EMULSIFIED ASPHALT	404.65				
		383	141	123	123	192	258	336			1556		TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT	406.27				
		1	1	1	1	1	1	1			7		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	406.29				
	1										1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
		62	20	22	22	18	18	32			194		GAL	WATER REPELLENT, SILANE	514.10				
			33	42	42	34	34	30			215		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
		2188	561	503	503	578	578	1054			5965		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
		60	60	76	76	60	60	60			452		LF	JOINT SEALER, HOT POURED	524.11				
		2344	731	747	737	758	758	1197			7272		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
		16	5	5	5	5	5	8			49		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10				
		16	5	5	5	5	5	16			57		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
		33	10	10	10	10	10	16			99		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
		19695	5047	4530	4530	5199	5199	9490			53690		SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
		10	10	10	10	10	10	10			70		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20				
		5	5	5	5	5	5	5			35		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
		5	5	5	5	5	5	5			35		HR	TRUCK RENTAL	608.37				
		200	100	60	60	100	100	160			780		HR	TRUCK-MOUNTED ATTENUATOR	608.45				
		2	2	2	2	2	2	2			14		EACH	ENERGY ABSORPTION ATTENUATOR	621.56				
		150	150	150	150	150	150	150			1050		LF	TEMPORARY TRAFFIC BARRIER	621.90				
		150	150	150	150	150	150	150			1050		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
		2640	680	600	600	700	700	1280			7200		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
									1		1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
	1										1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
		1									1		LS	TRAFFIC CONTROL (I91 - BRIDGE NO. 33S)	641.10				
			1								1		LS	TRAFFIC CONTROL (I91 - BRIDGE NO. 34S)	641.10				
				1							1		LS	TRAFFIC CONTROL (I91 - BRIDGE NO. 35N)	641.10				
					1						1		LS	TRAFFIC CONTROL (I91 - BRIDGE NO. 35S)	641.10				
						1					1		LS	TRAFFIC CONTROL (I91 - BRIDGE NO. 39N)	641.10				
							0.5	0.5			1		LS	TRAFFIC CONTROL (I91 - BRIDGES NO. 39S & 40S)	641.10				
		1	1	1	1	1	1	1			7		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
		1	1	1	1	1	1	1			7		EACH	PORTABLE ARROW BOARD	641.16				
		1075	410	299	299	573	759	981			4396		LF	6 INCH WHITE LINE	646.214				
		860	328	239	239	458	607	785			3516		LF	6 INCH YELLOW LINE	646.215				
		1075	410	299	299	573	759	981			4396		LF	TEMPORARY 6 INCH WHITE LINE	646.620				
		1175	1175	1175	1175	1175	1175	1175			8225		LF	TEMPORARY 6 INCH WHITE LINE, TYPE II TAPE	646.621				
		860	328	239	239	458	607	785			3516		LF	TEMPORARY 6 INCH YELLOW LINE	646.630				
		1175	1175	1175	1175	1175	1175	1175			8225		LF	TEMPORARY 6 INCH YELLOW LINE, TYPE II TAPE	646.631				
		65	25	18	18	34	45	59			264		EACH	LINE STRIPING TARGETS	646.76				
															PROJECT NAME: WINDSOR - HARTLAND PROJECT NUMBER: IM MEMB (I4)				
															FILE NAME: ...03-04-quantity sheet.dgn PROJECT LEADER: G. BOGUE DESIGNED BY: M. CHENETTE QUANTITY SHEET 1				
															PLOT DATE: 8/5/2009 DRAWN BY: E. ALLING CHECKED BY: M. CHENETTE SHEET 3 OF 39				