STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES					TOTALS		DESCRIPTIONS			
ROADWAY	EROSION CONTROL	I-89 BR NO. 13-1	I-89 BR NO. 14-1	I-89 BR NO. 14-2	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND
1						1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	
			20			20		CY	SOLID ROCK EXCAVATION	203.16	
		15	20	15		50		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27	
1						1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	
		108	190	174		472		CY	STRUCTURE EXCAVATION	204.25	
		70	201	387		658		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	
		23	49	71		143		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34	
		1979	4439	8688		15106		LB	REINFORCING STEEL	507.15	
			40			40		LF	DRILLING AND GROUTING DOWELS	507.16	
		2	4	6		12		GAL	WATER REPELLENT, SILANE	514.10	
		5	25	36		66		CY	REMOVAL OF CONCRETE OR MASONARY	529.25	
			47			47		CY	CONCRETE, CLASS C	541.30	
		10	10	10		30		CY	CONCRETE, CLASS D	541.31	
		23	37	31		91		CY	STONE FILL, TYPE IV	613.13	
				33		33		LF	CHAIN-LINK FENCE, 6 FEET	620.12	
				6		6		EACH	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 6 FEET	620.21	
				33		33		LF	REMOVAL OF EXISTING FENCE	620.55	
120						120		HR	UNIFORMED TRAFFIC OFFICERS	630.10	
48						48		HR	FLAGGERS	630.15	
					1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	
1						1		LS	MOBILIZATION/DEMOBILIZATION	635.11	
		1				1		LS	TRAFFIC CONTROL (I-89 BR NO. 13-1)	641.10	
			1			1		LS	TRAFFIC CONTROL (I-89 BR NO. 14-1)	641.10	
				1		1		LS	TRAFFIC CONTROL (I-89 BR NO. 14-2)	641.10	
6						6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
		8	10	17		35		SY	GEOTEXTILE UNDER STONE FILL	649.31	
	117					117		SY	GEOTEXTILE FOR SILT FENCE	649.51	
	2					2		LB	SEED	651.15	
	14					14		LB	FERTILIZER	651.18	
	0.06					0.06		TON	AGRICULTURAL LIMESTONE	651.20	
	0.06					0.06		TON	HAY MULCH	651.25	
	8					8		CY	TOPSOIL	651.35	
	1					1		LS	EPSC PLAN	652.10	
	48					48		HR	MONITORING EPSC PLAN	652.20	
	1					1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

PROJECT NAME: SHARON
PROJECT NUMBER: IM CULV (18)

FILE NAME: **Quantity Sheet** PLOT DATE: **7/8/2009**
PROJECT MANAGER: **DMB** DRAWN BY: **RPH**
DESIGNED BY: **RPH** CHECKED **BRC**
QUANTITY SHEET #1 SHEET **5** OF **36**