STATE OF VERMONT
AGENCY OF TRANSPORTATION

# QUANTITY SHEET 2

| SUMMARY OF ESTIMATED QUANTITIES | | | | | | | | | | | | | | TOTALS | | DESCRIPTIONS | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | ROADWAY | EROSION CONTROL | I-89 BR NO. 13-1 | I-89 BR NO. 14-1 | I-89 BR NO. 14-2 | FULL C.E. ITEMS | GRAND TOTAL | FINAL | UNIT | ITEMS | ITEM NUMBER | ROUND |
| | | | | | | | 136 | | | | | 136 | | SY | PERMANENT EROSION MATTING | 653.21 | |
| | | | | | | | 2013 | | | | | 2013 | | LF | PROJECT DEMARCATION FENCE | 653.55 | |
| | | | | | | | | 10 | 10 | 10 | | 30 | | CY | SPECIAL PROVISION (CONTROLLED DENSITY (FLOWABLE) FILL) | 900.608 | |
| | | | | | | | | 273 | | | | 273 | | LF | SPECIAL PROVISION (ALUMINUM PIPE LINER) (60") (EXISTING 72" PIPE) | 900.640 | |
| | | | | | | | | | 481 | | | 481 | | LF | SPECIAL PROVISION (ALUMINUM PIPE LINER) (102") (EXISTING 114" PIPE) | 900.640 | |
| | | | | | | | | | | 560 | | 560 | | LF | SPECIAL PROVISION (ALUMINUM PIPE LINER) (132") (EXISTING 144" PIPE) | 900.640 | |
| | | | | | | | | 200 | 200 | 200 | | 600 | | LF | SPECIAL PROVISION (TEST BORINGS) | 900.640 | |
| | | | | | | | | 1 | | | | 1 | | LS | SPECIAL PROVISION (TEMPORARY ACCESS ROAD AND STAGING AREAS, CULVERT)(I-89 BR NO. 13-1) | 900.645 | |
| | | | | | | | | | 1 | | | 1 | | LS | SPECIAL PROVISION TEMPORARY ACCESS ROAD AND STAGING AREAS, CULVERT)(I-89 BR NO. 14-1) | 900.645 | |
| | | | | | | | | | | 1 | | 1 | | LS | SPECIAL PROVISION (TEMPORARY ACCESS ROAD AND STAGING AREAS, CULVERT)(I-89 BR NO.14-2) | 900.645 | |
| | | | | | | | | 1 | | | | 1 | | LS | SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)(I-89 BR NO. 13-1) | 900.645 | |
| | | | | | | | | | 1 | | | 1 | | LS | SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)(I-89 BR NO.14-1) | 900.645 | |
| | | | | | | | | | | 1 | | 1 | | LS | SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)(I-89 BR NO.14-2) | 900.645 | |

| DETAILED SUMMARY OF QUANTITIES | | |
|---|---|---|
| QUANTITIES | UNIT | ITEMS |

PROJECT NAME: SHARON
PROJECT NUMBER: IM CULV (18)

FILE NAME: **Quantity Sheet**
PROJECT MANAGER: **DMB**
DESIGNED BY: **RPH**
**QUANTITY SHEET #2**

PLOT DATE: **7/8/2009**
DRAWN BY: **RPH**
CHECKED BY: **BRC**
SHEET **6** OF **36**