STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
NORTHBOUND MM 117.730 RT		1	48	48	16.00						2						X	X																W4-IR		SHS
NORTHBOUND MM 117.800 LT		1	36	12	3.00						2					X		X																R6-IR		SHS
NORTHBOUND MM 117.910 RT		1	42	30	8.75						2					X		X																I-2		E-131
NORTHBOUND MM 117.920 LT		1	36	36	9.00						2					X		X																R3-4		SHS
NORTHBOUND MM 117.960 RT		1	48	36	12.00						2						X	X																R8-7		SHS
NORTHBOUND MM 118.000 RT		1	12	48	4.00						1					X		X																D10-3		SHS
NORTHBOUND MM 118.035 RT		1 1	30 36	15 36	3.12 9.00						2						X	X																M3-1 WHITE ON BLUE M1-1	MOUNT M3-1 ABOVE M1-1		SHS SHS
NORTHBOUND MM 118.130 RT		1 1	48 24	48 18	16.00 3.00						2						X	X																VW-397 VP-396	MOUNT VW-397 ABOVE VP-396	46	 E-153B
NORTHBOUND MM 118.225 RT		1 1	48 48	60 48	20.00 16.00						2												2		X									R2-1 VR-141	MOUNT R2-1 ABOVE VR-141		SHS E-142
NORTHBOUND MM 118.380 RT		1	102	42		29.75	R				2																	2		270	W6X9		D2-2 FUSE PLATE BOLT TENSION = 12.0 KIPS	34	
							1					FT	FT	FT	FT	FT 99.75	FT 120		EA	LB	LB	LB		LB	LB 270	LB	LB								
					SF 119.87	SF 29.75	EA.	SF				FT			FT 219.75					LB			EA. 2	LB 270			EA. 2	EA.	LB. 270						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

NORTHBOUND TRAFFIC SIGN SUMMARY SHEET 19

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSSNB19.T

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 80 OF 221