STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
EXIT 22 RAMP D MM. 0.063 RT	HIGHGATE SPRS. 3 → WRONG WAY MOUNTED BACK TO BACK	1 1	72 36	12 24	6.00 ~~5.00~~ 6.00						2												2	X								DI-1A R5-1A		E-123 SHS
	GAS/DIESEL 3 → MOUNTED BACK TO BACK	1 1	72 24	10 24	5.00 4.00																											VD-502GD R9-4A	49	 SHS
	TO	1	24	12	2.00																											M4-5 BLACK ON WHITE		SHS
	SOUTH	1	24	12	2.00																											M3-3 BLACK ON WHITE		SHS
	7	1	24	24	4.00																											M1-4		SHS
	→	1	21	15	2.19																											M6-1R BLACK ON WHITE		SHS
EXIT 21 RAMP D MM. 0.081 RT	DO NOT ENTER MOUNTED BACK TO BACK	1 1	36 30	36 30	9.00 6.25						2					X		X															W6-3 R5-1		SHS SHS
EXIT 22 RAMP D MM. 0.106 RT	STOP	1	30	30	6.25						1					X		X															R1-1		SHS
												FT	FT	FT	FT	FT 45	FT		EA	LB	LB	LB		LB 228	LB	LB	LB								
					SF 52.69 ~~51.69~~	SF	EA.	SF				FT			FT 45					LB			EA. 2	LB 228				EA.	EA.						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

INTERCHANGE 22 TRAFFIC SIGN SUMMARY SHEET 5

PROJECT NAME: COLCHESTER-HIGHGATE
PROJECT NUMBER: IMG SIGN (17)

FILE NAME: 09A016.DGN
PROJECT LEADER: EPD
DESIGNED BY: BMB
PLOT FILE: 09A016TSSS22-5.1

PLOT DATE: 8/21/2009
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 190 OF 221