STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 22

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																					REMARKS	SIGN DETAIL	
												FLANGED CHANNEL			SQUARE STEEL (in)					TUBULAR ALUMINUM DIA (in)			TUBULAR STEEL DIA (in)					W-SHAPE STEEL						
		E A	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	lb/ft			1.75	2.0	2.5	ANCHOR	SLEEVE	3.0	4.0	4.0Mod	FND-ATION	3.0	3.5	4.0	5.0	FTG. SIZE		WEIGHT	POST SIZE	SIGN FRAME		
												lb/ft			lb/ft					lb/ft				lb/ft										
												1.12	2.0	3.0	1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6	24"	30"					
73.580 SB MED		1	12	36	3.00						1				X			1															OM-3L		
73.715 SB		1	48	48	16.00						2												2	X									W8-13		
73.870 SB		1	48	48	16.00																												VW-285	151	
	NEXT 2000 FT	1	30	24	5.00						2												2	X										151	
73.870 SB MED		1	48	48	16.00																												VW-285	151	
	NEXT 2000 FT	1	30	24	5.00						2												2	X										151	
73.960 SB		1	12	36	3.00						1				X			1															OM-3R		
73.960 SB MED		1	12	36	3.00						1				X			1															OM-3L		
74.000 SB		1	12	36	3.00						1					X		1															D10-2		E-139
74.060 SB		1	48	48	16.00																													151	
	ICING MAY OCCUR	1	42	24	7.00						2												2	X										151	
74.155 SB		1	48	48	16.00						2												2	X									W8-13		
74.350 SB MED		1	36	36	9.00						2					X		2															R3-4		
74.434 SB MED		1	36	36	9.00						2					X		2															R3-4		
75.000 SB		1	12	36	3.00						1					X		1															D10-2		E-139
76.000 SB		1	12	36	3.00						1					X		1															D10-2		E-139
76.040 SB MED		1	36	36	9.00						2					X		2															R3-4		
												FT	FT	FT	FT 38.0	FT 129.5	FT		EA.	LB	LB	LB		LB 1071.6	LB	LB	LB							
		SUBTOTALS SHEET 22			SF 142.00	SF	EA.	SF				FT			FT 167.5					LB			EA. 10	LB 1071.6				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WATERBURY - WINOOSKI
PROJECT NUMBER: IM G SIGN(18)

FILE NAME:	090124 tss main SB.xls	PLOT DATE:	10/27/2009
PROJECT LEADER:	CRB	DRAWN BY:	JH
DESIGNED BY:	BDB	CHECKED BY:	DAM
TRAFFIC SIGN SUMMARY SHEET # 22		SHEET 80	OF 174