

STATE OF VERMONT AGENCY OF TRANSPORTATION											QUANTITY SHEET 2									
SUMMARY OF ESTIMATED QUANTITIES											TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
	ROADWAY 91S	TRAINING	EROSION CONTROL	BRIDGE 43S	FULL C.E. ITEMS	ROADWAY 91N	BRIDGE 43N	ROADWAY RT 5	ROADWAY COMMON		GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS	
				1							1		EACH	PARTIAL REMOVAL OF STRUCTURE (SUPERSTRUCTURE 43S)	529.20					
				12			12				24		EACH	BEARING DEVICE ASSEMBLY, ELASTOMERIC PAD W/ EXT. LOAD PLATES	531.18					
							50				50		CY	CONCRETE, CLASS C	541.30					
														BEGIN OPTION AA						
						30					30		LF	18" CSP .064 (2-2/3 X 1/2)	601.0015					
						30					30		LF	18" CAAP .060 (2-2/3 X 1/2)	601.0215					
						30					30		LF	18" PCCSP .079 (2-2/3 X 1/2)	601.0416					
						30					30		LF	18" RCP CLASS III	601.0815					
						30					30		LF	18" CPEP	601.0915					
						30					30		LF	18" CPPP (SL)	601.2815					
														END OPTION AA						
						1					1		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18					
	1							1			2		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40					
								1			1		EACH	CAST IRON COVER WITH FRAME	604.55					
			280								280		MGAL	DUST CONTROL WITH WATER	609.10					
			2								2		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15					
	90					2					92		CY	STONE FILL, TYPE II	613.11					
								648			648		LF	GRANITE SLOPE EDGING	616.20					
								362			362		LF	VERTICAL GRANITE CURB	616.21					
	58					48					106		LF	BITUMINOUS CONCRETE CURB, TYPE A	616.305					
	4					2		5			11		EACH	STEEL MARKER POSTS	619.16					
								90			90		LF	REMOVING AND RESETTING FENCE	620.50					
	389.5					564.5					954		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20					
						58					58		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205					
						1					1		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50					
	1					5					6		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60					
	4					4					8		EACH	GUARDRAIL APPROACH SECTION TO CONCRETE BRIDGE RAILING, TL-3	621.747					
	100					75					175		LF	REMOVE AND RESET GUARDRAIL	621.75					
	375					650		300			1325		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80					
						1310		1600			2910		LF	TEMPORARY TRAFFIC BARRIER	621.90					
	810										810		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95					
	2250					2250					4500		HR	FLAGGERS	630.15					
					1						1		LS	FIELD OFFICE, ENGINEERS	631.10					
					1						1		LS	TESTING EQUIPMENT, CONCRETE	631.16					
					1						1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17					
					5000						5000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26					
		1040									1040		HR	EMPLOYEE TRAINEESHIP	634.10					
									1		1		LS	MOBILIZATION/DEMOBILIZATION	635.11					
						1					1		LS	TRAFFIC CONTROL (I-91 NORTHBOUND)	641.10					
	1										1		LS	TRAFFIC CONTROL (I-91 SOUTHBOUND)	641.10					

PROJECT NAME: HARTFORD	
PROJECT NUMBER: IM 09I-2(79)	
FILE NAME: sl2al32qs.dgn	PLOT DATE: I5-DEC-2014
PROJECT LEADER: K. HIGGINS	DRAWN BY: K. FRIEDLAND
DESIGNED BY: W. LAMMER	CHECKED BY: J. SALVATORI
QUANTITY SHEET 2	SHEET 8 OF 166