



PVC Coated Small Diameter Wire Rope
(Galvanized Aircraft Cable - GAC)



7 x 7
Steel Core



7 x 19
Steel Core

PVC Coated Small Diameter (Galvanized) Wire Rope				
Nominal Rope Diameter Inches (mm)	Nominal Coated Diameter Inches (mm)	Construction	Breaking Strength lbs (kN)	Approximate Weight lbs / ft (kg / m)
1/4 (6.4)	5/16 (7.9)	7x7	6,100 (27.1)	.106 (.157)
1/4 (6.4)	5/16 (7.9)	7x19	7,000 (31.1)	.110 (.164)
5/16 (7.9)	3/8 (9.5)	7x7	9,200 (40.9)	.167 (.249)
5/16 (7.9)	3/8 (9.5)	7x19	9,800 (43.6)	.173 (.259)
3/8 (9.5)	7/16 (11.1)	7x7	13,100 (58.3)	.236 (.350)
3/8 (9.5)	7/16 (11.1)	7x19	14,400 (64.1)	.243 (.361)

Per ASTM A1023-02 Table 9

Maccaferri reserves the right to amend product specifications without notice and specifiers are requested to check as to the validity of the specifications they are using.