




Wire Rope



6 x 19
Seale
IWRC



6 x 25
Filler Wire
IWRC



6 x 26
Warrington-Seale
IWRC

Wire Rope Classification 6x19 Bright or Drawn-Galvanized, IWRC, EIPS			
Nominal Diameter Inches (mm)	Construction EIPS	Minimum Break Strength EIPS Tons (kN)	Approximate Weight lbs / Ft (kg / m)
3/8 (10)	6x25 or 6x26	7.55 (67.1)	0.26 (.386)
1/2 (12)	6x25 or 6x26	13.3 (118.3)	0.46 (.687)
9/16 (14)	6x25 or 6x26	16.8 (149.4)	0.59 (.870)
5/8 (16)	6x25 or 6x26	20.6 (183.2)	0.72 (1.074)
3/4 (19)	6x25 or 6x26	29.4 (261.5)	1.04 (1.546)
7/8 (22)	6x25 or 6x26	39.8 (354)	1.42 (2.104)
1 (25)	6x25 or 6x26	51.7 (459.9)	1.85 (2.748)
1-1/8 (29)	6x25 or 6x26	65.0 (578.2)	2.34 (3.478)
1-1/4 (32)	6x25 or 6x26	79.9 (710.7)	2.89 (4.292)

Meets or exceeds federal specification RR-W-410 [latest revision] and or ASTM A1023
Minimum breaking strength for final-galvanized ropes 10 % lower than values listed per ASTM A1023.

Maccaferri reserves the right to amend product specifications without notice and specifiers are requested to check as to the validity of the specifications they are using.

MACCAFERRI

www.maccaferri-usa.com

HEADQUARTERS:

10303 Governor Lane Boulevard
Williamsport, MD 21795-3116
Tel: 301-223-6910
Fax: 301-223-6134
info@maccaferri-usa.com

AREA OFFICES:

AZ, Phoenix
CA, Sacramento
FL, Coral Gables
MD, Williamsport

MO, St. Louis
NJ, Iselin
NM, Albuquerque
PR, Caguas

TX, Lewisville
WA, Seattle

© 2014 Maccaferri, Inc. Printed in the USA