

DRILLING & BLASTING OF SOLID
ROCK SUBGRADE, ITEM 115
NB 3273+00-3277+00
SB 3272+00-3284+00
NB 3279+00-3284+00
SB 3274+01-3282+50 (Rest Area)
NB 3280+15-3283+00

PROPERTY LINE FENCE/STEEL POSTS, MOD
Item 583-II
SB 3268+00-3284+00 LT
NB 3268+00-3284+00 RT

* JUTE MATTING-ITEM 623
SB 3268+00-3270+50 RT
SB 3283+00-3284+00 LT

INDIVIDUAL WATER SOURCES
DUG SPRING S.B.L. 3274± - 700'± LT
WATER POOL S.B.L. 3279± - 700'± LT
NOTE: * DENOTES ITEMS TO BE
INCLUDED IN STAGE II CONSTRUCTION

Rev S.B.
A 3°19'00" LT
D 0°15'00"
R 22918.82
T 668.52
L 1326.67
E 9.61
Bank 1/4" per ft.

FOR CONSTRUCTION DETAILS OF UTILITY RELOCATION
AND REST AREA, SEE FOLLOWING SHEET

BM #150
ASMD ELEV
649.689

BM #151
ASMD ELEV
651.949

Rev S.B.
R 1.3276+18.13
3276+18.13
POT 3276+17.92

CONTROL OF ACCESS IS COMPLETE ON THIS SHEET

GEORGIA-FAIRFAX-FAIRFIELD-ST ALBANS

189-3(14)

Sheet 16 of 213

STA. 3268=MM110.78