

PLAN
Scale 1" = 40'

Profile
Scale 1" = 10'

Present Bridge Data
 Conc. Box 12" curbs & wingwalls
 1 Span = 6.7'
 OA Span = 6.0'
 Roadway Width = 21.0'
 Clear Height = 4.5'
 No Aprons, Brook 4' to 6' wide

GENERAL NOTES:

1. The General Note pertaining to Specifications, Materials, and Construction is shown on Standard Drawing SCB-DI-67. Other notes shown on this Standard, which pertain to this Project not otherwise shown on these plans are: 16, 19, 20.
2. Item 401-B; Concrete Class "B" Modified shall be used on this project. All exposed edges of concrete shall be chamfered 1"x1". Minimum clear cover for reinforcing steel shall be 3" in the invert slab and 2" elsewhere.
3. Item 440; Water Repellent shall be applied both outside exposed surfaces of the concrete headwalls and wingwalls.
4. Item 103-B; Solid Rock Excavation Modified is used on this project to cover the cost of removing the existing RC Box top slab and walls, wingwalls, and the concrete bridge railing.

