

TRAFFIC SIGN SUMMARY SHEET

1986

TRAFFIC SIGN SUMMARY SHEET																									1986	
MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS	EXISTING SIGNS		NEW AND SALVAGED SIGNS					EXISTING POSTS				NEW SIGN POSTS										REMARKS	FOR SIGN DETAIL SHEET	
			TO BE SALVAGED REMOVE (EA.)	RETAIN (X)	NEW "A" (S.F.)	NEW "B" (S.F.)	SALV. SIGN EA.	SALV. T.S. (S.F.)	RET.	DRILL	REM.	SALV.	NUMBER OF POSTS	FLANGED CHANNEL		TUBULAR ALUMINUM		W SHAPED STEEL		FIG. SIZE		PLAN SHEET NUMBER	STD. SHEET NUMBER			
														2.0 LB./FT.	3.0 LB./FT.	3.0" Ø	3.0" □	4.0" Ø	4.0" Ø MOD.	POST SIZE	WEIGHT				24"	30"
0.70 RT.	T.I.S. * SEE T.I.S. REMARKS		* X	✓					* 8.0	✓			* 2			* X								* Item 680.20 MOD. NON-FED-PARTICIPATING		
0.70 RT.	T.I.S. *		* X	✓					* 8.0	✓																
0.84 LT.	SOUTH ✓ 100 ✓	24" X 12" ✓ 30" X 24" ✓			2.0 ✓ 5.0 ✓																		Mount on Retained Post		E-13 E-13	
0.86 LT.	STOP ✓							1 ✓					1 ✓	X ✓												
0.87 LT.	LEGAL LOAD LIMIT 24,000 POUNDS ✓	24" X 24" ✓			4.0 ✓								1 ✓	X ✓											E-15A	
0.88 RT.	NORTH ✓ 100 ✓	24" X 12" ✓ 30" X 24" ✓			2.0 ✓ 5.0 ✓								1 ✓	X ✓											E-13 E-13	
1.03 RT.	SPEED ZONE AHEAD ✓	24" X 30" ✓			5.0 ✓								1 ✓	X ✓											E-15B	
1.20 RT.	SPEED LIMIT 40 ✓	24" X 30" ✓			5.0 ✓																		Mount on Retained Post		E-15B	
1.20 LT.	SPEED LIMIT 50 ✓	24" X 30" ✓			5.0 ✓																				E-15B	
1.45 RT.	SPEED LIMIT 40 ✓	24" X 30" ✓			5.0 ✓																				E-15B	
1.49 RT.	◀ ✓ ▶ ✓	18" X 24" ✓ 18" X 24" ✓			3.0 ✓ 3.0 ✓								1 ✓	X ✓											E-19 E-19	
1.52 RT.	◀ ✓ ▶ ✓	18" X 24" ✓ 18" X 24" ✓			3.0 ✓ 3.0 ✓								1 ✓	X ✓											E-19 E-19	
1.52 RT.	▨ ✓	12" X 36" ✓			3.0								1 ✓	X ✓											TD #16	
1.52 LT.	▨ ✓	12" X 36" ✓			3.0 ✓																				TD #16	
1.53 RT.	▨ ✓	12" X 36" ✓			3.0 ✓																				TD #16	
1.53 LT.	▨ ✓	12" X 36" ✓			3.0 ✓																				TD #16	
1.54 RT.	◀ ▶	18" X 24" ✓ 18" X 24" ✓			3.0 ✓ 3.0 ✓								1 ✓	X ✓											E-19 E-19	
1.55 RT.	LEGAL LOAD LIMIT 24,000 POUNDS ✓	24" X 24" ✓			4.0 ✓								1 ✓	X ✓											E-15A	
1.64 LT.	WATCH FOR TURNING VEHICLES	36" X 36" ✓			9.0 ✓																		Mount on Retained Post		TD #16	
1.78 RT.	SPEED LIMIT 40 ✓	24" X 30" ✓			5.0 ✓																					
TOTALS			X		86.0 #			1 ✓	* 24.0	X	X	X	242 360 #													
FINAL LENGTHS ARE TO BE DETERMINED IN THE FIELD, POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE DESIGN DIVISION'S "SIGN POST DESIGN MANUAL".																										
PREPARED BY <u>J.B.</u> DATE <u>8-86</u> CHECKED BY _____ DATE _____ PROJ. <u>F</u> NO. <u>029-1(12)</u> <u>WATERBURY ~ STOWE</u> TRAFFIC SHEET NO. <u>12</u> SHEET <u>34</u> OF <u>108</u>																										

FINAL LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE DESIGN DIVISION'S "SIGN POST DESIGN MANUAL".

CHECKED BY _____ DATE _____
 PROJ. F NO. 029-1(12)
 WATERBURY ~ STONE
 TRAFFIC SHEET NO. 12 SHEET 34 OF 108