

REV STA. 223+48 - ASKEWED 76° 07' LT.
NEW 18" x 140" PCSP 0.064, CAAP 0.060"
OR REV CL. III W/ES @ INLET, PAD W/STN.
FULL TYPE X @ OUTLET 3' WIDE x 1' DEEP
EXTENDING 12' BEYOND END OF CULVERT.

REV STA. 223+48 - EXIST. 18" RCP
(TO BE REMOVED)

REV STA. 223+35 LT.
END 6" x 295' U.D. W/ FB @
REV STA. 220+53 & 223+03

SURV. 223+46 = REV. 223+48.88
ASKEWED @ 77°-18' LT.

REV STA. 223+03 LT.
INSTALL FLUSHING BASIN

REV STA. 222+05 LT.
BEGIN STONE LINED DITCH
TYPE I, 6" W
BEGIN SPECIAL DITCH

SURV. 223+00 = REV. 223+02.98

POLE # 162
101
SURV. STA. 222+70

SURV. 222+50 = REV. 222+53.10

REV STA. 222+37 LT.
CONSTRUCT DRIVE (14' WIDE)
NEW 16" x 52" CSP 0.064" OR
RCP CLASS III W/ES @ OUTLET

REV STA. 222+40 LT.
EXIST. 18" C&MP
(TO BE REMOVED)

REV STA. 222+12 LT.
END SPECIAL DITCH
END STONE LINED DITCH
TYPE I, 6" W

SURV. 222+34 = REV. 222+37.14

C = 0.50 Ft
F = 533.50 Ft
R = 0.50 Ft

C = 0.50 Ft
F = 263.50 Ft
R = 0.50 Ft

STA. 222+34	STA. 223+46
TOWN MARSHFIELD	
PROJECT F	NO. 028-3(28)
SHEET 249	OF 352 SHEETS
HORIZ. AND VERT. SCALE	
0 10 20	
VT. SURVEY CONSULTANTS DATE 10/86	