

SOIL CLASSIFICATION

AASHTO	
A1	Gravel and Sand
A3	Fine Sand
A2	Silty or Clayey Gravel and Sand
A4	Silty Soil - Low Compressibility
A5	Silty Soil - Highly Compressible
A6	Clayey Soil - Low Compressibility
A7	Clayey Soil - Highly Compressible

UNIFIED SOIL SYSTEM

GW/GP	Clean Gravels (Few Fines)
GM/GC	Gravels (Appreciable Fines)
SW/SP	Clean Sands (Few Fines)
SM/SC	Sand (Appreciable Fines)
ML/CL	Low Plastic Silts & Clays
OL	Low Plastic Organic Silt
MH/CH	High Plastic Silts & Clays
OH	High Plastic Organic Silt
PT	Highly Organic Soils

MOISTURE

DESCRIPTIVE TERM	OBSERVED IN FIELD	% ± BY ANALYSIS
Dry	No Visible Water	<10
Moist	Damp	10-20
Moist to Wet	Moist to Wet	21-50
Wet	Visible Water	51-70
Saturated		>70

ROCK QUALITY DESIGNATION

R.Q.D.	ROCK DESCRIPTION
<.25	Very Poor
.25 to .50	Poor
.51 to .75	Good
.76 to .90	Good
>.90	Excellent

SHEAR STRENGTH

UNDRAINED SHEAR STRENGTH IN P.S.F.	CONSISTENCY
<250	Very Soft
250-500	Soft
500-1000	Med. Stiff
1000-2000	Stiff
2000-4000	Very Stiff
>4000	Hard

CORRELATION GUIDE OF "N" TO DENSITY/CONSISTENCY

DENSITY (GRANULAR SOILS)	CONSISTENCY (COHESIVE SOILS)
N DESCRIPTIVE TERM	N DESCRIPTIVE TERM
<5 Very Loose	<2 Very Soft
5-10 Loose	2-4 Soft
11-24 Med. Dense	5-8 Med. Stiff
25-50 Dense	9-15 Stiff
>50 Very Dense	16-30 Very Stiff
	31-60 Hard
	>60 Very Hard

COMMONLY USED SYMBOLS

▼	Water Elevation
⊕	Standard Penetration Boring
⊙	Auger Boring
⊖	Rod Sounding
S	Sample
N	Standard Penetration Test
	Blow Count Per Foot For:
	2" O.D. Sampler
	1 3/4" I.D. Sampler
	Hammer Weight Of 140 Lbs.
	Hammer Fall Of 30"
VS	Field Vane Shear Test
US	Undisturbed Soil Sample
B	Blast
DC	Diamond Core
MD	Mud Drill
WA	Wash Ahead
HSA	Hollow Stem Auger
AX	Core Size 1 1/8"
BX	Core Size 1 5/8"
NX	Core Size 2 1/8"
M	Double Tube Core Barrel Used
LL	Liquid Limit
PL	Plastic Limit
PI	Plasticity Index
NP	Non Plastic
W	Moisture Content (Dry Wgt. Basis)
D	Dry
M	Moist
MTW	Moist To Wet
W	Wet
Sat	Saturated
Ba	Boulder
Gr	Gravel
Sa	Sand
Sl	Silt
Cl	Clay
HP	Hardpan
Le	Ledge
NLTD	No Ledge To Depth
CNPF	Can Not Penetrate Further
TLOB	To Ledge Or Boulder
NR	No Recovery
Rec.	Recovery
%Rec.	Percent Recovery
RQD	Rock Quality Designation
CBR	California Bearing Ratio
<	Less Than
>	Greater Than

COLOR

bik	Black	pnk	Pink
bl	Blue	pu	Purple
brn	Brown	rd	Red
dk	Dark	tn	Tan
gr	Gray	wh	White
gn	Green	yel	Yellow
lt	Light	mtc	Multicolored
or	Orange		

NOTE: SEE SHT 137 OF 319 FOR BORING LOCATION

HOLE NO. SB-1 STA. 202+06 OFFSET 11' RT
 DRILLER Green Mountain Boring
 LOG APPROVED BY WLR
 DATE START 1/20/87 FINISH 1/22/87
 SURFACE ELEVATION 522.5

DEPTH	BLOWS ON CASING	STANDARD PENETRATION	LIQUID LIMIT	PLASTICITY INDEX	MOISTURE	COLOR	CLASSIFICATION AND PROPERTIES OF SOIL AND ROCK
70	20	M					Silty clay into silt into silty sand
80	18	M					Silty clay
90	16	M					Silty clay
100	16	M					Silty clay
10	6	M					Fine silty sand
20	28	W					Silt w/trace of clay
30	18	W					Silt w/trace of clay
40	9	M					Silty clay
50	8	M					Silty clay
60	12	M					Silty clay w/small stone
70	20	N					Silty clay into silt into silty sand

B.O.F.

APPROX. PILE PEN

SB-1

HOLE NO. SB-2 STA. 201+95 OFFSET 25' LT
 DRILLER Green Mountain Boring
 LOG APPROVED BY WLR
 DATE START 1/22/87 FINISH 1/27/87
 SURFACE ELEVATION 521.8

DEPTH	BLOWS ON CASING	STANDARD PENETRATION	LIQUID LIMIT	PLASTICITY INDEX	MOISTURE	COLOR	CLASSIFICATION AND PROPERTIES OF SOIL AND ROCK
70	11	M					Silty clay
80	12	D					Silty sand w/stones
90	13	M					Silty sand w/stones into silty clay
100	13	M					Silty sand w/trace of clay and small stones
10	9	D					Fine silty sand
20	18	M					Silt w/trace of clay into fine sand & silt w/pebbles
30	18	W					Silty sand into fractured stone particles
40	6	M					Silt w/trace of clay
50	11	M					Silty clay varved w/sand
60	10	M					Sandy silt
70	11	M					Silty clay

B.O.F.

APPROX. PILE PEN

SB-2

GENERAL NOTES

- The subsurface explorations shown herein were made between _____ and _____ by the Agency.
- Soil and rock classifications, properties and descriptions are based on engineering interpretation from available subsurface information by the Agency and may not necessarily reflect actual variations in subsurface conditions that may be encountered between individual boring or sample locations.
- Observed water levels and/or conditions indicated are as recorded at the time of exploration and may vary according to the prevailing rainfall, methods of exploration and other factors.

4. Engineering judgement was exercised in preparing the subsurface information presented herein. Analysis and interpretation of subsurface data was performed and interpreted for Agency design and estimating purposes. Presentation of the information in the Contract is intended to provide the Contractor access to the same data available to the Agency. The subsurface information is presented in good faith and is not intended as a substitute for personal investigation, independent interpretation, independent analysis or judgement by the Contractor.

- Pictorial structure details shown on the boring plan layout or soils profile are for illustrative purposes only and may not accurately portray final contract details.

PARE ENGINEERING CORPORATION
 Engineers - Planners - Landscape Architects
 8 Blackstone Valley Place, Lincoln, RI 02865
 401/334/4100

STATE OF VERMONT
AGENCY OF TRANSPORTATION

Town Of	POWNA	Bridge No. 6
Highway No.	ROUTE 346	Log Sta.
		Surv. Sta. 201+74
BORING INFORMATION SHEET		
Designed By	J.S.J.	Drawn By F.F.
Checked By	Date	Bridge Design Supervisor
	P.D.M.	Date
PROJECT	POWNA	PROJECT NO. RS0107(7)
L.G.C. info.	QSAH30,25BORINGSTD.DGN	R. S. HAUP 2-85
Bridge Sheet No.	BR 602	Sheet 139 of 319