STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
BRIGHTON: 374+60.0, RT	BRIDGE 29 VT 114	1	6	8	0.33						1				X			X															SIGN ID CODE VD-701		E-134
374+88.0, LT	BRIDGE 29 VT 114	1	6	8	0.33						1				X			X															SIGN ID CODE VD-701		E-134
375+91.0, RT	STEVENS LOOP						1				1					X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKETS REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
	STOP 1140 0504 0712	1	6	10	0.42		1																										BACK-TO-BACK SIGN ID CODE VD-700		- E-138
376+25.0, RT	13'-5"	1	36	36	9.00						2					X		X															SIGN ID CODE W12-2		E-155
	2 MILES	1	30	12	2.50																												SIGN ID CODE W16-3a	68	
378+50.0, RT		1	30	30	6.25						1					X		X															SIGN ID CODE W1-4R	68	
	40 M.P.H.	1	18	18	2.25																												SIGN ID CODE W13-1		E-155
378+79.0, LT	ISLAND POND 3 LYNDONVILLE 27	1 1	72 72	12 12	6.00 6.00						2					X		X															SIGN ID CODE D1-1 SIGN ID CODE D1-1		E-123 E-123
380+17.0, RT	↑ NORTON 13 ↑ CANAAN 27	1 1	72 72	12 12	6.00 6.00						2					X		X															SIGN ID CODE D1-1 SIGN ID CODE D1-1		E-123 E-123
	← MORGAN CORNER 6 ← DERBY CENTER 15	1 1	72 72	12 12	6.00 6.00																												SIGN ID CODE D1-1 SIGN ID CODE D1-1		E-123 E-123
												LF	LF	LF	LF 28	LF 112	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
												LF			LF 140					LB			EA.	LB				EA.	EA.	LB					
				TOTALS	SF 57.08	SF	EA. 2	SF																											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #3

PROJECT NAME: BRIGHTON - WARREN GORE

PROJECT NUMBER: STP 2724(1)S

FILE NAME: p07c216.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p07c216tss3.i

PLOT DATE: 31-OCT-2011 11:52
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 60 OF 107