

**STATE OF VERMONT
AGENCY OF TRANSPORTATION**

COMPOSITE QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTORS				DETAILED SUMMARY OF QUANTITIES				
STP 291.3(1)										NH 2948(1)										
						ROADWAY (MAJOR COLLECTOR)	TRAINING (MAJOR COLLECTOR)	BRIDGE (MAJOR COLLECTOR)	FULL C.E. ITEMS (MAJOR COLLECTOR)	ROADWAY (PRINCIPAL ARTERIAL)	FULL C.E. ITEMS (PR ARTERIAL)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
															BEGIN OPTION DD					
										190		190		LF	DURABLE 6 INCH YELLOW LINE, THERMOPLASTIC	646.432	12			
										190		190		LF	DURABLE 6 INCH YELLOW LINE, EPOXY PAINT	646.433	12			
										190		190		LF	DURABLE 6 INCH YELLOW LINE, POLYUREA	646.434	12			
															END OPTION DD					
															BEGIN OPTION EE					
										25		25		LF	DURABLE 8 INCH YELLOW LINE, THERMOPLASTIC	646.452	1			
										25		25		LF	DURABLE 8 INCH YELLOW LINE, EPOXY PAINT	646.453	1			
										25		25		LF	DURABLE 8 INCH YELLOW LINE, POLYUREA	646.454	1			
															END OPTION EE					
															BEGIN OPTION FF					
						340				300		640		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	34			
						340				300		640		LF	DURABLE 24 INCH STOP BAR, EPOXY PAINT	646.483	34			
						340				300		640		LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	34			
															END OPTION FF					
															BEGIN OPTION GG					
						69				127		196		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-			
						69				127		196		EACH	DURABLE LETTER OR SYMBOL, EPOXY PAINT	646.493	-			
						69				127		196		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-			
															END OPTION GG					
															BEGIN OPTION HH					
										50		50		LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	3			
										50		50		LF	DURABLE CROSSWALK MARKING, EPOXY PAINT	646.503	3			
										50		50		LF	DURABLE CROSSWALK MARKING, POLYUREA	646.504	3			
															END OPTION HH					
						215400				25200		240600		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	2420			
						213900				21400		235300		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	2236			
										600		600		LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	42			
										380		380		LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	24			
						680				600		1280		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	68			
						207				190		397		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
										100		100		LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	6			
						3400				550		3950		EACH	LINE STRIPING TARGETS	646.76	EST.			
										610		610		LF	PAINTED CURB	646.81	10			
										1770		1770		SF	PAINTED ISLAND	646.82	22			
						7070				15		7085		SY	GEOTEXTILE UNDER STONE FILL	649.31	76.5			
						630						630		SY	GEOTEXTILE FOR SILT FENCE	649.51	5			
						1710				35		1745		LB	SEED	651.15	0.8			
						14250				250		14500		LB	FERTILIZER	651.18	EST.			
						60				1		61		TON	AGRICULTURAL LIMESTONE	651.20	EST.			

PROJECT NAME: WEATHERSFIELD
PROJECT NUMBER: STP 2913(I) / NH 2948(I)

FILE NAME: I0c228.dgn	PLOT DATE: 2/7/2013
PROJECT LEADER: PTS	DRAWN BY: WWG
DESIGNED BY: NLL	CHECKED BY: PTS
IPARM FILE NAME: pI0C228_I2	SHEET 12 OF 234