

STATE OF VERMONT AGENCY OF TRANSPORTATION												QUANTITY SHEET 3													
SUMMARY OF ESTIMATED QUANTITIES												TOTALS		DESCRIPTIONS						DETAILED SUMMARY OF QUANTITIES					
								ROADWAY	TRAINING	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS					
								1250				1250		LB	SEED	651.15	EST.			TOPSOIL					
								2500				2500		LB	FERTILIZER	651.18	EST.								
								10				10		TON	AGRICULTURAL LIMESTONE	651.20	EST.	371	SY	ITEM DETAIL SHEET 4					
								10				10		TON	HAY MULCH	651.25	EST.	3.8	SY	PROJECT DETAILS SHEET 2					
								400				400		CY	TOPSOIL	651.35	25.2	25.2	SY	ROUNDING					
								15400				15400		SY	GRUBBING MATERIAL (2")	651.40	422.2	400	SY	TOTAL					
								1440				1440		SY	GRUBBING MATERIAL (6")	651.40	24.6			TEMPORARY EROSION MATTING					
								2050				2050		SY	TEMPORARY EROSION MATTING	653.20	48.6	1415.4	SY	ITEM DETAIL SHEET 4					
								4300				4300		LF	BARRIER FENCE	653.50	36	586	SY	DITCH CLEANING DETAIL SHEET					
								3200				3200		LF	EROSION LOG	653.60	11	48.6	SY	ROUNDING					
								390				390		SF	TRAFFIC SIGNS, TYPE A	675.20	4.86	2050	SY	TOTAL					
								295				295		LB	TUBULAR STEEL SIGN POST	675.33	6								
								1242				1242		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-								
								2				2		EACH	FOUNDATION FOR TUBULAR STEEL POST	675.43	-			SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE					
								73				73		EACH	REMOVING SIGNS	675.50	-	9971	TON	WEARING					
								6				6		EACH	ERECTING SALVAGED SIGNS	675.60	-	3326	TON	LEVELING					
								51				51		EACH	DELINEATOR WITH STEEL POST	676.10	-	143.9	TON	SIDEROADS					
								40				40		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-	287	TON	PULL OFFS					
								1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-	72.1	TON	ROUNDING					
								4				4		EACH	SPECIAL PROVISION (CORING CONCRETE)	900.620	-	13800	TON	TOTAL					
								5				5		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620	-								
								1				1		EACH	SPECIAL PROVISION (GNSS CONSTRUCTION INSPECTION EQUIPMENT)	900.620	-								
								3955				3955		LF	SPECIAL PROVISION (BARRIER FOR TEMPORARY TRAFFIC PROTECTION)	900.640	-								
								13248				13248		LF	SPECIAL PROVISION (BOX BEAM GUARDRAIL W/7 FEET POSTS)	900.640	6								
								95				95		LF	SPECIAL PROVISION (VERTICAL GRANITE CURB, MOUNTABLE)	900.640	-								
								1				1		LS	SPECIAL PROVISION (GPS MACHINE CONTROL GRADING)	900.645	-								
								122000				122000		SY	SPECIAL PROVISION (COLD MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT)	900.675	1474								
								1330				1330		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	39.2								
								114000				114000		SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE)	900.675	766								
								123000				123000		SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE, PORTLAND CEMENT)	900.675	1856								
								75				75		SY	SPECIAL PROVISION (STAMPED COLORED CONCRETE APRON, 8 INCH)	900.675	3.6								
								3100				3100		TON	SPECIAL PROVISION (AGGREGATE TO MEET COLD MIXED GRADATION)	900.680	49								
								10				10		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.								
								13800				13800		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	72.1								
								21500				21500		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE, COLD MIX)	900.680	415.4								
								1850				1850		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR BASE STABILIZATION)	900.680	32.8								
								215				215		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR COLD MIXED RECYCLING)	900.680	12								
								46000				46000		TON	SPECIAL PROVISION (RSB SUPPLEMENTAL AGGREGATE MATERIAL)	900.680	931								
								770				770		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-IH OR CRS-IH)	900.683	11.9								
																		PROJECT NAME: HANCOCK							
																		PROJECT NUMBER: STP 2923 (1)							
																		FILE NAME: z10c252quant.dgn							
																		PLOT DATE: 3/18/2015							
																		PROJECT LEADER: C. LATHROP							
																		DESIGNED BY: B. MARTIN							
																		CHECKED BY: C. LATHROP							
																		QUANTITY SHEET 3							
																		SHEET 19 OF 207							