

DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF SQUARE STEEL NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION							
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	SHSM	PROJECT SHEET #	STANDARD SHEET #				
																	(LB / FT)				(LB / FT)												
																	1.88	2.42	3.35		7.60	9.00	10.80			14.60							
NORWICH US5 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS											
		F	M6-2	21	15							1																					
		F	M4-5	24	12			2.00						2		X					2	WHITE ON BLUE	X										
		F	M1-1	24	24			4.00														X											
		F	M6-2	21	15			2.19														X											
		F	M3-3	24	12			2.00														X											
		F	M1-4	24	24			4.00														X											
		F	M6-2	21	15			2.19														X											
SB	2.457	F	D1-1M	72	12		<=== 45 DEG HANOVER N.H. 1			1			X																				
		F	D1-1A	72	10		NORWICH 1 ==>> 45 DEG			1																							
		F	D1-1A	72	12		WHITE RIVER JCT 6 ==>> 45 DEG			1																							
SIGN SUMMARY SHEET							SHEET TOTALS				16.38	0.00	3	0	0	1	0	0	2	30			0	0.0	0.0	0.0	0.0	PROJECT NAME: NORWICH - FAIRLEE					
											SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB	PROJECT NUMBER: STPG SIGN (34)					
																											FILE NAME: 10C334			PLOT DATE: 5/2/2011			
																											PROJECT MANAGER: A. GAMBLE			DRAWN BY: D.CROSSLEY			
VERMONT AGENCY OF TRANSPORTATION																											DESIGNED BY: D.CROSSLEY			CHECKED BY: QAU			
							TOWN DIRECTIONAL TOTALS				160.0	0.0	13.0	0.0	0.0	35	0.0	0.0	23	345.0			0	0.0				NORWICH U.S. 5 SOUTHBOUND 6			SHEET 18 OF 65		