STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES									TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						580				580		LF	4 INCH WHITE LINE	646.20				
						73040				73040		LF	4 INCH YELLOW LINE	646.21				
								720		720		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							170			170		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							130			130		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							5			5		LB	SEED	651.15				
							5			5		LB	SEED, WINTER RYE	651.17				
							40			40		LB	FERTILIZER	651.18				
							1			1		TON	AGRICULTURAL LIMESTONE	651.20				
							1			1		TON	HAY MULCH	651.25				
							30			30		CY	TOPSOIL	651.35				
								20		20		SY	GRUBBING MATERIAL	651.40				
							1			1		LS	EPSC PLAN	652.10				
							40			40		HR	MONITORING EPSC PLAN	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							110			110		SY	TEMPORARY EROSION MATTING	653.20				
							2			2		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
							60			60		CY	VEHICLE TRACKING PAD	653.35				
							600			600		LF	PROJECT DEMARCATION FENCE	653.55				
						174.91				174.91		SF	TRAFFIC SIGNS, TYPE A	675.20				
						451				451		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
						26				26		EACH	REMOVING SIGNS	675.50				
						2				2		EACH	SETTING SALVAGED POSTS	675.61				
								38		38		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET)(FPQ)	900.608				
								30		30		LF	SPECIAL PROVISION (PRE-EXCAVATION OF INTEGRAL ABUTMENT PILES, EARTH)	900.640				
								25		25		LF	SPECIAL PROVISION (PRE-EXCAVATION OF INTEGRAL ABUTMENT PILES, ROCK)	900.640				
								344		344		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE, NEXT D BEAMS)(NEXT 36D)	900.640				
						1				1		LS	SPECIAL PROVISION (CPM SCHEDULE)	900.645				
								1		1		LS	SPECIAL PROVISION (REMOVAL OF TEMPORARY BRIDGE AND APPROACHES)	900.645				
						1				1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645				
						1				1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(N.A.B.I.)	900.650				
						1				1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I)	900.650				
						1				1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I)	900.650				
						195				195		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANITITY)	900.680				

PROJECT NAME: BARNARD
PROJECT NUMBER: ER BRF 0241(39)

FILE NAME: s10c410qs.dgn
PROJECT LEADER: K. HIGGINS
DESIGNED BY: W. LAMMER
QUANTITY SHEET 2

PLOT DATE: 17-SEP-2013
DRAWN BY: W. LAMMER
CHECKED BY: J. SALVATORI
SHEET 6 OF 39