

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES					
										ROADWAY	ROADWAY (NO FEDERAL PART.)	FULL C.E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
										1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			COLD PLANING-BITUMINOUS PAVEMENT
										1000			1000		CY	EARTH BORROW	203.30	EST.	116073	SY	MAINLINE
										118000			118000		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	1055	872	SY	SIDEROAD APRONS
										15000			15000		LF	MILLED RUMBLE STRIPS (CENTERLINE)	213.10	512	1055	SY	ROUNDING
										2500			2500		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	12	118000	SY	TOTAL
										180			180		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	4			SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
																BEGIN OPTION AA					WEARING COURSE TYPE IVS
										1250			1250		CWT	EMULSIFIED ASPHALT (RS-1)	404.65	36	10153	TON	LEVELING COURSES PROFILE DEFICENCIES - TYPE IVS
										1250			1250		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683	36	342	TON	1/2" LEVEL- TYPE IVS
																END OPTION AA			3422	TON	INTERMEDIATE COURSE TYPE IVS
										1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-	86	TON	SIDE ROADS
										14400			14400		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	320	77	TON	TYPE IVS
										1			1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-	320	TON	ROUNDING
										1			1		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-	14400	TON	TOTAL
										1			1		LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-			
										1			1		LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-			
										8			8		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-			
										1			1		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-			
										1			1		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	-			
										30			30		HR	POWER GRADER RENTAL	608.15	EST.			
										110			110		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
										20			20		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE II (PNEUMATIC HAMMER)	608.26	EST.			
										30			30		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
										60			60		HR	POWER BROOM RENTAL, TYPE II	608.31	EST.			
										220			220		HR	TRUCK RENTAL	608.37	EST.			
										20			20		HR	LOADER RENTAL, TYPE I	608.40	EST.			
										1350			1350		CY	STONE FILL, TYPE I	613.10	22			
										3550			3550		LF	REMOVAL OF EXISTING CURB	616.41	23			
										111			111		EACH	YIELDING MARKER POSTS	619.17	EST.			
										1100			1100		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	25			
										38			38		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-			
										2			2		EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.51	-			
										60			60		EACH	REPLACE GUARDRAIL POST ASSEMBLY	621.76	3			
										170			170		EACH	REPLACE GUARDRAIL BEAM UNIT	621.77	1			
										1500			1500		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	40			
										700			700		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
										2000			2000		HR	FLAGGERS	630.15	EST.			
												0.34	0.34		LS	FIELD OFFICE, ENGINEERS	631.10	-			
												1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
												0.34	0.34		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			