

STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET 1

BEGIN STATION	END STATION	POS.	203.30 EARTH BORROW	604.412 REHAB. DI, CB OR MH CLASS I	613.10 STONE FILL, TYPE I	616.35 TREATED TIMBER CURB	616.41 REMOVAL OF EXIST. CURB	619.17 YIELD MARKER POSTS	621.80 REMOVE & DISP. OF G.R.	649.51 GEOT. FOR SILT FENCE	651.35 TOPSOIL	653.20 TEMP. EROSION MATTING	676.10 DELINE. WITH STEEL POSTS	676.12 REMOVAL OF EXIST. DELINE.	900.640 BOX BEAM G.R. W/7 FT POSTS	900.680 AGG. SHOULD., RAS	REMARKS
			CY	EACH	CY	LF	LF	EACH	LF	SY	CY	SY	EACH	EACH	LF	TON	
BROOKFIELD				7				103			94					426	FOR USE AS DIRECTED BY ENGINEER
MM 0.285	MM 0.418	RT	50						480		10	50	2	2	702		SEE VTRANS STD GI-BM FOR END SECTION DETAILS
MM 2.636	MM 2.776	RT															EXTEND START BY 40' AND TRAILING END 184' RETAIN EXISTING GUARDRAIL
MM 2.649	MM 2.771	LT															RETAIN EXISTING GUARDRAIL
MM 2.918	MM 3.000	RT															RETAIN EXISTING GUARDRAIL
MM 2.926	MM 2.998	LT															RETAIN EXISTING GUARDRAIL
MM 3.119	MM 3.329	LT	50						615		10	50	2	2	684		SEE VTRANS STD GI-BM FOR END SECTION DETAILS EXTEND TRAILING END 25'
MM 3.206	MM 3.283	LT			150		407			181							REMOVE CURBING & INSTALL TYPE I STONE BLANKET
MM 3.407	MM 3.465	LT	50						300		10	50	2	2	306		SEE VTRANS STD GI-BM FOR END SECTION DETAILS
MM 3.414	MM 3.453	LT			76		206			92							REMOVE CURBING & INSTALL TYPE I STONE BLANKET
MM 3.422	MM 3.667	RT	50						1300		10	50	2	2	1296		SEE VTRANS STD GI-BM FOR END SECTION DETAILS
MM 3.430	MM 3.667	RT			462		1251			557							REMOVE CURBING & INSTALL TYPE I STONE BLANKET
MM 3.678	MM 3.862	RT	50						970		10	50	2	2	972		SEE VTRANS STD GI-BM FOR END SECTION DETAILS
MM 3.678	MM 3.855	RT			345		935			416							REMOVE CURBING & INSTALL TYPE I STONE BLANKET
MM 3.698	MM 3.800	LT	50						540		10	50	2	2	594		SEE VTRANS STD GI-BM FOR END SECTION DETAILS EXTEND TRAILING END 50' TO CURVE UP SIDE ROAD
MM 4.366	MM 4.479	RT	50						580		10	50	2	2	594		SEE VTRANS STD GI-BM FOR END SECTION DETAILS EXTEND LEADING END 6'
MM 4.379	MM 4.473	RT			183		496			221							REMOVE CURBING & INSTALL TYPE I STONE BLANKET
MM 4.571	MM 5.031	RT	50						2425		10	50	2	2	2430		SEE VTRANS STD GI-BM FOR END SECTION DETAILS EXTEND LEADING END 6'
MM 4.873	MM 5.024	RT				797											REPLACE TIMBER CURB
MM 5.092	MM 5.164	RT	50						375		10	50	2	2	378		SEE VTRANS STD GI-BM FOR END SECTION DETAILS
MM 5.103	MM 5.155	RT			101		275			123							REMOVE CURBING & INSTALL TYPE I STONE BLANKET
MM 5.092	MM 5.164	LT	50						375		10	50	2	2	378		SEE VTRANS STD GI-BM FOR END SECTION DETAILS
SUBTOTAL			500	7	1317	797	3570	103	7960	1590	194	500	20	20	8334	426	PROJECT NAME: BROOKFIELD PROJECT NUMBER: STP 2960(I) FILE NAME: z15v0231ds.dgn PROJECT LEADER: C.LATHROP DESIGNED BY: S.SOLLA ITEM DETAIL SHEET PLOT DATE: 4/26/2016 DRAWN BY: O.DALMER CHECKED BY: C.LATHROP SHEET 159 OF 202
ROUNDING			-	-	-	3	-	-	15	35	-	-	-	-	-	14	
TOTAL			500	7	1317	800	3570	103	7975	1625	194	500	20	20	8334	440	