

~~591/60 - 594/64 Rt~~
~~593/83 - 599/85 Lt~~ *
~~590/50 - 600/23 Lt~~
~~596/39 - 599/91 Rt~~
591 + 75 - 594 + 55 Rt
593 + 89 - Bridge Lt
593 + 81 - Bridge Rt
599 + 59 - 600 + 07 Lt
599 + 59 - 599 + 75 Rt

CLEARING & GRUBBING

CONSTRUCT DRIVES
590+65 Rt. ✓
596+90 Rt. ✓
600+00 Rt. ✓

CONSTRUCT APPROACH
594+00~595+50 Lt. ✓

WOOD GUIDE POSTS
Lt 16' c/c
589+08 ~ 589+40
Rt
589+48 ~ 590+28

REMOVAL & DISPOSAL OF
PRESENT GUARD RAIL
~~591+92 - 594+10 R+~~
~~598+94 - 600+62 R+~~
~~599+96 - 600+17 L+~~
592+00 - 594+00 R+

A.A. WEBSTER
#7D 0.12 ACRE ±
STA. 584+00-590+00 LT.

#7E 0.04 ACRE ±
STA. 587+50 - 591+50 RT.

A.A. WEBSTER
#7F 0.09 ACRE ±
STA. 591+52 - 595+50 RT.

Δ 33° 59' R
 D 6°
 R 955.4
 T 291.49
 L 566.4
 E 43.6
Bank 3/4" per ft.

7G 0.06 ACRE ±
STA. 595 + 50 - 599 + 00 RT.

ALFRED B. DARLING
#9B 0.05 ACRE ±
STA. 599+45 - 601+22 LT.

ALFRED B. DARLING
#9A 0.076 ACRE ±
STA. 600+15 - 602+50 RT.

PARCEL	INSTRUMENT	DATE	GRANTOR	GRANTEE	RECORDED TOWN OF	Book	Page	Date	REMARKS
9ABCD	WDOE	11-8-55	ALFRED B. DARLING	ST OF VT	LYNDON	45	436	2-2-56	see also sheets 25 & 26
9EFGHI	WDOE	11-8-55	ALFRED B. DARLING	ST OF VT	BURKE	26	307-308	2-2-56	see also sheets 26, 27, 29 & 31

Sheet No	Index of Sheets (Bridge Only)
24 of	173 Plan and Profile
41 "	173 Preliminary Information Sheet
42 "	173 Bridge Details, Abutment No. 1
43 "	173 Bridge Details, Abutment No. 2
44 "	173 Standard Structure Sheet 918 30(H-20), Superstructure
45 "	173 Bridge Details - Curb and Rolling
46 "	173 Reinforcing Steel Schedule (Bridge)
55 "	173 Standard Structure Sheet-948-46 (Cable Rail End Units)
57 "	173 Standard Structure Sheet-9811 (Barricades, Signs & Lights) Bridges
58 "	173 Standard Structure Sheet-5820 Details C,D,H (Mod), J,K, & L.
107 "	173 Cross Sections

Item No.	Item	Unit	Quant.
106-C	Unclassified Channel Excavation	c.y.	55
107	Structure Excavation	c.y.	138
401-B	Concrete Class B (Mod)	c.y.	124
402	Reinforcing Steel	lb.	16490
403-A	Structural Steel	lb.	47080
441	Temporary Bridge	l.s.	1
442	Removal of Present Superstructure	l.s.	1
501	Furnishing Equipment for Driving Piles	l.s.	1
502-B	Treated Timber Piling	l.f.	1080
556-C	Granite Bridge Curb-Type 1	l.f.	108
572	Bridge Railing	l.f.	100

