STATE OF VERMONT
AGENCY OF TRANSPORTATION

CHESTER TRAFFIC SIGN SUMMARY SHEET 8

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR STEEL Ø (In) FOUND-ATION	3.0 lb/ft 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGNS FRAMED REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
CHESTER VT. ROUTE 11: C 269+71.0, LT		1	30	30	6.25						1					X		X												SIGN ID CODE W11-2 SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	X		
		1	24	12	2.00																									SIGN ID CODE W16-7P SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	X		
C 269+75.0, RT		1	30	30	6.25						1					X		X												SIGN ID CODE W11-2 SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	X		
		1	24	12	2.00																									SIGN ID CODE W16-7P SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	X		
C 269+89.0, RT	Grafton St / Main St	1	30	8	1.67						1					X		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TWO TOP MOUNTING BRACKETS REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		84	
		1	24	8	1.33																									DOUBLE SIDED SIGN, SIGN ID CODE D3-1		84	
C 270+44.0, RT	STOP 0110 1407 0512	1 1	30 6	30 10	6.25 0.42						1					X		X												BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700	X		T-44
C 270+75.0, RT	JCT EAST	1 1	21 24	15 12	2.19 2.00						2					X		X											#1A	SIGN ID CODE M2-1, GREEN ON WHITE SIGN ID CODE M3-2, GREEN ON WHITE	X X		
	VERMONT 103 VERMONT 11	1 1	30 24	24 24	5.00 4.00																									SIGN ID CODE M1-5, GREEN ON WHITE SIGN ID CODE M1-5, GREEN ON WHITE			E-136B E-136B
C 270+90.0, LT	SOUTH WEST	1 1	24 24	12 12	2.00 2.00						2					X		X											#2	SIGN ID CODE M3-3, BLACK ON WHITE SIGN ID CODE M3-4, GREEN ON WHITE	X X		
	35 VERMONT 11	1 1	24 24	24 24	4.00 4.00																									SIGN ID CODE VM1-5A, BLACK ON WHITE SIGN ID CODE M1-5, GREEN ON WHITE			E-136C E-136B
	← ↑	1 1	21 21	15 15	2.19 2.19																									SIGN ID CODE M6-1L, BLACK ON WHITE SIGN ID CODE M6-3, GREEN ON WHITE	X X		
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF	LF 112	LF		EA		LB	LB	LB	LB									
		TOTALS			SF 55.74	SF	EA.	SF				LF				LF 112				EA.		LB			EA.	EA.	LB						

CHESTER TRAFFIC SIGN SUMMARY SHEET #8

PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
PROJECT NUMBER: STP 2952(1)

FILE NAME: z13c518tss_seg01.dgn
PROJECT LEADER: D. GOZALKOWSKI
DESIGNED BY: A. HAWKINS
PLOT DATE: 3/27/2015
DRAWN BY: A. KIRBY
CHECKED BY: J. SHIELDS
SHEET 66 OF 309