

WOOD GUARD RAIL REQUIRED.

LEFT			
Sta.	575+50 to 575+74	Length	24 ft.
"	588+17 " 588+41	"	24 "
"	582+88 " 583+12	"	24 "

NEW CULVERTS REQUIRED

Sta. 575+62	18" Reinf. Concrete Pipe Culvert	32 Lin. ft.
	Concrete Class B (1-2X-4)	2.4 cu yds.
	Reinforcing Steel	54 lbs.
Sta. 588+23	18" Reinf. Concrete Pipe Culvert	32 Lin. ft.
	Concrete Class B (1-2X-4)	2.4 cu yds.
	Reinforcing Steel	54 lbs.
Sta. 582+50	18" Reinf. Conc. Pipe Culvert	32 Lin. ft.
	Concrete Class B (1-2X-4)	2.4 cu yds.
	Reinforcing Steel	54 lbs.

SUB-1

Sta. 588+00

PLAN
1/4" = 100'
N.W.M.
G.H.C.

12/16
A.D.
1/2" = 100'

