

CABLE GUARD RAIL REQUIRED

LEFT

Sta. 883+60 to 885+60 - 200 ft

RIGHT

Sta. 883+60 to 885+60 Length 200 ft

CULVERT REPAIRS REQUIRED.

Sta. 884+74 2x3 Concrete Box Culvert.

Build New floor & Extend.

Class A Concrete 4.9 cu yd.

Reinforcing Steel 326 pounds.

DRIVEWAY CULVERT REPAIRS REQUIRED.

Sta. 882+70 Build New Headers.

Class B Concrete (4-2x5) 1.1 Cu yd.

SUB-BASE OF GRAVEL

Sta. 882+00 to 886+00

" 886+00 to 897+00

