

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

MORETOWN STP EGC-RSEGC RS 0167(9)								MORETOWN - MIDDLESEX BRS 0167(II)								MORETOWN STP EGC-RSEGC RS 0167(9) AND MORETOWN - MIDDLESEX BRS 0167(II)					MORETOWN STP EGC-RSEGC RS 0167(9) DETAILED SUMMARY OF QUANTITIES			MORETOWN - MIDDLESEX BRS 0167(II) DETAILED SUMMARY OF QUANTITIES					
TRAIN- ING	LAND- SCAPING	R.O.W.	FULL E+C ITEMS	BRIDGE 300 SERIES	EROSION CONTROL	ROADWAY	TOTALS	TRAIN- ING	LAND- SCAPING	R.O.W.	UTILIT.	FULL E+C ITEMS	EROSION CONTROL	BRIDGE 100 SERIES	BRIDGE 200 SERIES	ROADWAY	TOTALS	GRAND TOTALS	UNIT	ITEMS	ITEM NO.	ROUND- ING	QUANTITIES	UNIT	ITEMS	QUANTITIES	UNIT	ITEMS	
						7.5 0.5	0.5									0.5	0.5	1	HR	TRUCK RENTAL (NOT A BID ITEM)	608.37								
						3 0.5	0.5									0.5	0.5	1	HR	LOADER RENTAL, TYPE I (NOT A BID ITEM)	608.40								
						5 0.5	0.5									0.5	0.5	1	HR	LOADER RENTAL, TYPE II (NOT A BID ITEM)	608.41								
						1480 215	215									55	55	270	MGAL	DUST CONTROL W/ WATER	609.10	EST.							
						3,125 3	3									1	1	4	TON	DUST AND ICE CONTROL W/ CALCIUM CHLORIDE	609.15	EST.							
														16			16	EA	ROCK BOLT ANCHOR (ULT. STRENGTH = 25K MIN.)	612.30									
					260,345	685 415	460					11					11	471	CY	STONE FILL, TYPE I	613.10								
						1123,8525	525									5	5	530	CY	STONE FILL, TYPE II	613.11	1							
						371.9-C,0								300			300	300	CY	STONE FILL, TYPE IV	613.13								
																210	210	210	LF	GRANITE SLOPE EDGING	616.20	10							
																1100	1100	1100	LF	VERTICAL GRANITE CURB	616.21	31							
						1112 1150	1150											1150	LF	TREATED TIMBER CURB	616.35	20							
																3	3	3	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	EST							
						5 7	7									1	1	8	EA	RELOCATE MAILBOX, SINGLE SUPPORT	617.10								
						2 3	3									1	1	4	EA	RELOCATE MAILBOX, MULTIPLE SUPPORT	617.12								
						0 55	55									15	15	70	EA	BOUNDARY MARKERS	619.10	EST.							
						3 78	78									3	3	81	EA	YIELDING MARKER POSTS	619.17	3							
						0 5	5									2	2	7	EA	REMOVING AND RESETTING PROPERTY MARKERS	619.20	EST							
																90	90	90	LF	CHAIN-LINK FENCE, 8 FT. (MOD.)	620.13								
																24	24	24	LF	GATE FOR CHAIN-LINK FENCE, 8 FT. (MOD.)	620.17								
																16	16	16	EA	BRACING ASSEMBLY FOR CHAIN LINK FENCE, 8 FT.(MOD)	620.22								
						3	3											3	EA	DRIVE GATE FOR WOVEN WIRE FENCE	620.30								
						6 3	3											3	EA	STEEL BRACE FOR WOVEN WIRE FENCE	620.40								
						0 1150	1150									110	110	1260	LF	REMOVAL OF EXISTING FENCE	620.55	18							
						3183 3175	3175											3175	LF	STEEL BEAM GUARD RAIL (W/ STEEL POSTS)	621.20	13							
						9	9											9	EA	MODIFIED ECCENTRIC LOADER TERMINAL W/ WOOD POSTS (MELT)	621.52								
						50	50									50	50	100	LF	ALUMINUM APPROACH RAIL (MOD # 1)	621.74								
						0 75	75									200	200	275	LF	ALUMINUM APPROACH RAIL (MOD # 2)	621.74								
						84,3										100	100	2100	LF	REMOVAL & DISP. OF GUARD RAIL	621.80	34							
						1925 2000	2000												140	LF	ALUMINUM APPROACH RAIL (MOD #3)	621.74							
						120 40	140												140	LF	INCLINOMETER	623.30							
						116 40	140												140	LF	GROUND WATER OBSERVATION WELL	623.50							
						418 388	388											388	LF	SLEEVES FOR UTILITIES (6" PVC) (SCHEDULE 40)	625.10								
																31	31	31	LF	PVC SEWER PIPE (3'')	628.35								
																						SQUAD LEADER DELLA SANTA			DESIGN FILE NO. /SQDB/I8E132/DEI32.DGN				
																						IPARM FILE DEI32Q4.I			DATE PLOTTED 31-MAY-2000				
																						MORETOWN RS 0167(9) AND MORETOWN-MIDDLESEX BRS 0167(II)							
																						SHEET 6 OF 243 SHEETS							