

222+45.4
BEGIN REMOVAL & DISPOSAL
OF EXISTING GUARD RAIL

222+50
Begin Removal of Portland Cement
Concrete Pavement (See Plan for
25' Solid Rock Excavation)

223+89 Rt.
Removing Signs (Fish & Game Sign Post and
Sign if attached)
223+89 Rt. 35's
Setting Salvaged Posts
(This item shall be used to reset
the Fish and Game Sign Post. This
will include a new concrete footing
of the same size that exists and
any hardware necessary. Sign shall
also be erected if it was attached
at the time of removal.)

223+53 Rt.
Begin Std. Steel Beam Guard Rail
w/ Wood Posts, Type II

223+28 ~ 223+53 Rt.
Breakaway Cable Terminal for
Std. Steel Beam Guard Rail w/
Wood Posts, Type II

223+10 Rt.
Construct Drive
Section A-A

Guard Rail Details
Scale 1" = 10' Feet

FROM STA. 222+50 TO STA. 223+50
PROJECT NAME HIGHGATE
NO. BR50285(1)S
SURVEYED BY FANTONI
SHEET 32 OF 64 SHEETS
PLOTTED 11/24/81
SEPT. 1981

222+50
END APPROACH - BEGIN PROJECT BR5 0285(1) S

SCALE 1" = 10' FEET