FED. ROAD DIST. NO. | STATE | F.A.S PROJ. NO. | FISCAL YEAR | SHEET NO. | TOTAL SHEETS
9 | VT | 18-B(1) | 1940 | 17 | 67
PARCEL INSTRUMENT DATE GRANTOR GRANTEE RECORDED REMARKS
BRIDPORT
A Q.C. 8-18-39 DAVID & BERNICE JACKSON ST. OF VT BOOK 20 PAGE 238-39 DATE 8-24-39
Removing and Resetting Fence
230+00 Lt. ~ 230+50 Lt.
Temporary Barbed Wire Fence (4 Strand)
230+00 Lt. ~ 230+50 Lt.
217+00 Lt. ~ 218+00 Lt.
REMOVAL OF EXISTING FENCE
LT RT
230+00 ~ 230+50
217+00 - 218+00
Δ 14°25' Lt
D 4°
R 1432.7'
T 181.2'
L 360.4'
E 11.4
Δ = 14°-27'-00"
D = 4°
R = 1432.40
T = 181.59
L = 361.25
E = 11.89
L.C. = 360.29
P.T. 220+74.7
REV P.T. 220+43.84
REV P.O.T. 220+74.70
EQ = -30.86'
P.C. 217+14.3
REV P.C. 216+82.59
34"E (Remove)
8"Ash (Remove)
217+00 ~ 219+25 Lt.
Construct 8' Paved Shoulder & Special Ditch w/ Erosion Matting
See Typicals Previous Page
Ditching Paid Under Common Excavation
230+25 24" RCP
Retain Relay 8' and Extend w/
New 24" x 8' RCPCL III w/ Stone Fill Type II pad
& CRADLE HEADWALL NEW 80" + 8' PCCSP
230+25 Lt 30" RCP
Remove, Clean Out and Relay 20'
w/ New Concrete Cradle HW @ Inlet
Stone Fill Type II pad @ Outlet
N
DAVID JACKSON
N 6°51' E
12" AC
15" Ash
3-6" Ash
Gate
MARY L. & T.D. SUNDERLAND
BRIDPORT 217+00 ~ 233+00
MM 1.31 ~ MM 1.62
227+95 24" CMP
Retain
230+25 Rt. 24" RCP
RETAIN
232+00 Rt. 15" CMP
Retain
SHOREHAM - BRIDPORT - ADDISON
F017-1(2)
SHEET 143 OF 420
SHEET 143 OF 477