

PROJECT LENGTHS AND ITEM QUANTITIES

ITEM DESCRIPTION

ITEM DESCRIPTION	Length	Width	Overlay	Depth	Option											
					Aggregate Shoulders	Aggregate Shoulders	Emulsified Asphalt	Bituminous Concrete Pavement	Power Grader Rental	Power Excavator Rental	Truck Rental	Uniformed Traffic Officers	Flaggers	Mob.lization		
ITEM NO.	FT	FT	IN		402.10	402.12	404.65	406.25	608.15	608.25	608.30	608.37	630.10	630.15	635.10	
IT	FT	FT	IN		CY	TON	CWT	TON	HR	HR	HR	HR	HR	HR	LS	
MM 0.000	740	26	1 1/4		89	156	2	148	12	12	10	12	130	200	0.07	Includes Shoulders
0.140								42								Level Course
MM 0.140	1040	20	1 1/4		125	219	6	160								Includes Shoulders
0.337								45								Level Course
MM 0.337	3575	24	1 1/4		430	752	7	662								Includes Shoulders
1.014								185								Level Course
MM 1.014	791	30	1 1/4		40	70	3	183								Includes Shoulders
1.164								51								Level Course
Drives + Approaches					29	51		16								
Rounding					2	7	2	8	-	-	-	-	-	-	-	
TOTALS					715	1255	20	1500	12	12	10	12	130	200	0.07	

PROJECT Ripton

NO. HMA 2864

SHEET 7 OF 8 SHEETS
SHEET 55 OF 75 SHEETS