# QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

## APPROXIMATE SUMMARY OF QUANTITIES

* – POSSIBLE ON-PROJECT STAGING AREA

| STAGING AREA * | CITY WATER AND SEWER NON-PART. | CITY WATER AND SEWER PART. | E & C | EROSION CONTROL | ROADWAY PARTIC. | TRAINING | STRUCTURES | LANDSCAPING | QUANTITY GRAND TOTAL | UNIT | DESCRIPTION OF ITEMS | ITEM NUMBER | ROUNDING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 573 | 467 | | | | | | | 1040 | LF | DUCTILE IRON PIPE, CEMENT-LINED (MOD)(8" CL-51) | 629.24 | – |
| | 4274 | 512 | | | | | | | 4786 | LF | DUCTILE IRON PIPE, CEMENT-LINED (MOD)(12" CL-51) | 629.24 | – |
| | 10 | 2 | | | | | | | 12 | EA | EXTENSION SERVICE BOX AND CURB STOP (3/4" OR 1") | 629.25 | – |
| | 4 | | | | | | | | 4 | EA | EXTENSION SERVICE BOX AND CURB STOP (1 1/2") | 629.25 | – |
| | 3 | | | | | | | | 3 | EA | EXTENSION SERVICE BOX AND CURB STOP (2") | 629.25 | – |
| | | 2 | | | | | | | 2 | EA | GATE VALVE WITH VALVE BOX (6") | 629.27 | – |
| | 5 | 3 | | | | | | | 8 | EA | GATE VALVE WITH VALVE BOX (8") | 629.27 | – |
| | 17 | 5 | | | | | | | 22 | EA | GATE VALVE WITH VALVE BOX (12") | 629.27 | – |
| | 11 | | | | | | | | 11 | EA | HYDRANT | 629.28 | – |
| | 8 | | | | | | | | 8 | EA | RELOCATE HYDRANT | 629.29 | – |
| | 2 | 6 | | | | | | | 8 | EA | TAPPING SLEEVE & VALVE WITH VALVE BOX (8x8) | 629.35 | – |
| | 1 | 1 | | | | | | | 2 | EA | TAPPING SLEEVE & VALVE WITH VALVE BOX (12x12) | 629.35 | – |
| | 7 | 2 | | | | | | | 9 | EA | CORPORATION STOP (3/4" OR 1") | 629.39 | – |
| | 3 | | | | | | | | 3 | EA | CORPORATION STOP (1 1/2") | 629.39 | – |
| | 3 | | | | | | | | 3 | EA | CORPORATION STOP (2") | 629.39 | – |
| | 1 | | | | | | | | 1 | LS | TRANSFER TO NEW SYSTEM-WATER SYSTEM | 629.42 | – |
| | 14 | 4 | | | | | | | 18 | EA | AIR RELEASE-WATER | 629.43 | – |
| | 3 | | | | | | | | 3 | EA | AIR RELEASE-WATER (MOD 1) (AIR RELEASE VALVE AND MANHOLE ASSEMBLY) | 629.43 | – |
| | | 1 | | | | | | | 1 | EA | AIR RELEASE-WATER (MOD 2) (6" BLOWOFF ASSEMBLY) | 629.43 | – |
| | | | | | | | | 1 | 1 | LS | IRRIGATION SYSTEM | 629.45 | – |
| | | | | | 9,000 | | | | 9,000 | HR | UNIFORM TRAFFIC OFFICERS | 630.10 | 360 |
| | | | | | 18,000 | | | | 18,000 | HR | FLAGGERS | 630.15 | 720 |
| | | | | | | 2,100 | | | 2,100 | HR | EMPLOYEE TRAINEESHIP | 634.10 | 20 |
| | | | | | 1 | | | | 1 | LS | MOBILIZATION | 635.10 | – |
| | | | | | 1 | | | | 1 | LS | TRAFFIC CONTROL (MOD) | 641.10 | – |
| | | | | | 4 | | | | 4 | EA | PORTABLE CHANGEABLE MESSAGE SIGN | 641.15 | – |
| | | | | | 2 | | | | 2 | EA | PORTABLE ARROW BOARD | 641.16 | – |
| | | | | | 22,000 | | | | 22,000 | LF | 4" WHITE LINES | 646.20 | 685 |
| | | | | | 16,000 | | | | 16,000 | LF | 4" YELLOW LINES | 646.21 | 172 |
| | | | | | 9,000 | | | | 9,000 | LF | DURABLE 4" WHITE LINE (THERMOPLASTIC) | 646.40 | 127 |
| | | | | | 14,500 | | | | 14,500 | LF | DURABLE 4" YELLOW LINE (THERMOPLASTIC) | 646.41 | 111 |
| | | | | | 10,600 | | | | 10,600 | LF | DURABLE 6" WHITE LINE (THERMOPLASTIC) | 646.414 | 96 |
| | | | | | 100 | | | | 100 | LF | DURABLE 8" WHITE LINE (THERMOPLASTIC) | 646.42 | 46 |

## DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | DESCRIPTION OF ITEMS |
|---|---|---|

## TYPE OF CONSTRUCTION

| STATIONS FROM | STATIONS TO | PAVEMENT WIDTHS 74'-0" C – C | TAPER | | | | | | EQUATIONS + | EQUATIONS – |
|---|---|---|---|---|---|---|---|---|---|---|
| TOTALS | | 5,680' | | | | | | | | |

| STATIONS | | FEET | MILES | REMARKS |
|---|---|---|---|---|
| TOTALS | | 7,303 | 1.39 | |

PROJECT NAME: SHELBURNE

PROJECT NUMBER: NH-EGC-019=4 (28)

4/4/03

QUANTITY DRAWING NO. 4

SHEET 17 OF 283 SHEETS