

STATION	TYPE	WIDTH @ ROW
126+87 LT	GRAV. W/ 5' PAVED APRON	12'
143+33 LT	GRAV. W/ 5' PAVED APRON	12'

401.10 AGGREGATE SURFACE COURSE
STA 144+80 - 145+75 LT

616.28 - CAST-IN-PLACE CONCRETE CURB, TYPE B
STA 126+75.0 - 126+79.3 LT
STA 126+95.2 - 127+69.0 LT
STA 127+33.8 - 127+69.0 RT
STA 129+57.3 - 145+75.0 RT
STA 129+57.3 - 129+59.3 LT
STA 142+50.0 - 143+23.9 LT
STA 143+41.6 - 145+75.0 LT

621.80 - REMOVAL AND DISPOSAL OF GUARDRAIL
STA 127+45 - 127+84 RT
STA 127+49 - 128+10 LT
STA 142+50 - 143+86 RT
STA 144+10 - 144+54 RT

618.10 - PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH
STA 127+33.8 - 127+69.0 RT
STA 129+57.3 - 129+59.0 RT
STA 144+80.0 - 145+75.0 LT

620.50 - REMOVING AND RESETTNG FENCE
STA 126+75 - 126+77 LT
STA 126+96 - 127+06 LT

621.205 - STEEL BEAM GUARDRAIL, GALVANIZED W/ 8 FEET POSTS
STA 127+11 - 127+50 RT
STA 127+14 - 127+51 LT
STA 142+50 - 143+69 RT
STA 129+75 - 130+05 RT

621.60 ANCHOR FOR STEEL BEAM GUARDRAIL
STA 127+11 RT
STA 127+14 LT
STA 130+05 RT

900.670 - SPECIAL PROVISION (PRECAST CONCRETE GRAVITY RETAINING WALL)
STA 144+65 - 145+75 LT

900.640 - SPECIAL PROVISION (BRIDGE RAILING, TEXAS)
STA 127+69 - 129+57 LT
STA 127+68 - 129+57 RT

NOTES:

- SEE SHEETS TSL-1 THROUGH TSL-4 TRAFFIC SIGNS, AND PAVEMENT MARKING DETAILS.
- SEE SHEETS DP-1 THROUGH DP-8 FOR DRAINAGE PLANS AND DETAILS.
- SEE CROSS-SECTION SHEETS FOR DRIVEWAY CONSTRUCTION DETAILS. ALL DRIVES SHALL BE PAVED 5' BEYOND THE EDGE OF SHOULDER REGARDLESS OF DRIVEWAY MATERIAL.
- SEE TYPICAL SECTION SHEETS FOR APPROACH CONSTRUCTION DETAILS.
- APPROXIMATE LOCATION OF WATER LINE RELOCATION. WATER LINE SHOWN FOR REFERENCE ONLY AND IS NOT PART OF THIS CONTRACT.
- SEE TSP 1 FOR TRAFFIC SIGNAL LAYOUT AND DETAILS.
- HOUSE REMOVALS INCLUDING SEWER STRUCTURES AND LEACH FIELDS IS NOT PART OF THIS CONTRACT AND SHALL BE COMPLETED BY OTHERS PRIOR TO THE PROJECT START DATE.
- RAILING ON TOP OF RETAINING WALL SHALL BE INCLUDED IN THE UNIT PRICE BID FOR 900.670 SPECIAL PROVISION (PRECAST CONCRETE GRAVITY RETAINING WALL)
- STONE WALL MAY BE REMOVED BY CONTRACTOR FOR THE PURPOSE OF POSITIONING CONSTRUCTION EQUIPMENT, WITH APPROVAL FROM THE ENGINEER, IF DEEMED NECESSARY. IF WALL IS REMOVED, PAYMENT WILL BE INCIDENTAL TO 635.11 MOBILIZATION/DEMOBILIZATION.

900.640 - SPECIAL PROVISION (BRIDGE APPROACH RAILING, GALVANIZED HDSB WITH HANDRAIL)
STA 127+50 - 127+69 RT
STA 127+51 - 127+69 LT
STA 129+57 - 129+66 LT
STA 129+57 - 129+75 RT

900.640 - SPECIAL PROVISION (CONCRETE ENCASED DUCT BANK, 1-4 DUCTS)
STA 143+65 - 145+75 RT

618.30 - DETECTABLE WARNING SURFACE
STA 144+84 LT
STA 144+84 RT

PLANT, ALBERT A., JR. & CATHERINE A.

JOHNSON, EDWARD H.

HUDSON, SHERRI - GINA

STATE OF VERMONT
FORMERLY; PARKER, JOYCE & CLICHE, CLINT E.

HEDGES, DEANE F. & RAYLENE E.

STATE OF VERMONT
FORMERLY; NICHOLSON, DOUGLAS & CORINE

STATE OF VERMONT
FORMERLY; PARKER, JOYCE & CLICHE, CLINT E.

BAMFORTH, JANICE DEGOOSH & GLEN CHARLES

BAMFORTH, JANICE DEGOOSH & GLEN CHARLES

PLANTE, BETH W.

THEODORE G. HEDGES & SONS, INC.
d/b/a CRYSTAL SPRINGS WATER CO.

PLANTE, BETH W.

DODGE, LAWRENCE B. & BONNIE

THIS PROJECT SUBJECT TO
STORMWATER
PERMIT #4251-INDS.R

LINES SHOWN ON THIS PLAN AS EXISTING
PROPERTY LINES P/L ARE BELIEVED TO
BE ACCURATE BUT SHOULD NOT BE RELIED
UPON FOR PURPOSES UNRELATED TO THE
STATE OF VERMONT'S ACQUISITION OF LAND
AND RIGHTS FOR THIS PROJECT.

FOR R.O.W.
USE ONLY

PROJECT NAME: EAST MONTPELIER
PROJECT NUMBER: BRP 037-1(7)

FILE NAME: r98b252.lay2.dgn
PROJECT LEADER: M. SARGENT
DESIGNED BY: STANTEC
ROW LAYOUT SHEET 2 OF 4

PLOT DATE: 15-SEP-2015
DRAWN BY: T. POLK
CHECKED BY: R. CLOUTIER
SHEET 145 OF 158

