

STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

RICHMOND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL 0/(in)				SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL			
				WIDTH	HEIGHT			“A”	“B”	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 lb/ft	2.00 lb/ft	2.50	FOUNDATION	3.00	3.50 lb/ft	4.00			5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
NB	MM 1.931, RT	A	W2-2R	30	30			6.25							I		X						INSTALL NEW SIGN AND POST 238 FT SOUTH OF THE CENTER OF BESAW RD	X					
		A	W16-8P	24	8			1.33															INSTALL NEW SIGN BENEATH SIDE ROAD INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT		10				
NB	MM 2.033, RT	D	RI-1	30	30			6.25					X		X	I		X						REMOVE STOP SIGN AND POST AND INSTALL NEW SIGN AND POST AT SAME LOCATION (GRANDVIEW DR)	X				
NB	MM 2.041, RT	A/B	D3-1	42	12			3.50					X		X									INSTALL NEW SIGN ABOVE STOP SIGN ON THE SAME POST		10			
NB	MM 2.071, RT	A	W7-1	30	30			6.25					X		X	I		X						INSTALL NEW SIGN AND POST OPPOSITE POLE# 1875	X				
SB	MM 2.186, LT	F	R2-1	24	30			5.00								I		X						INSTALL NEW SIGN AND POST 180 FT SOUTH OF THE CENTER OF GRANDVIEW DR	X				
SB	MM 2.530, LT	F	WI-2	30	30			6.25								I		X						INSTALL NEW SIGN AND POST 25 FT NORTH OF POLE# 56-50/32	X				
SB	MM 2.610, LT TO MM 2.550, LT	F E		6	8		(10) TYPE II - 6" X 8" WHITE DELINEATORS	3.33								5	X							INSTALL 5 DELINEATORS BACK-TO-BACK (10 TOTAL) 70 FT APART GOING NORTH. INSTALL THE FIRST ONE 60 FT NORTH OF POLE# 57-50/34		7			
NB	MM 2.977, RT	A	R2-1	24	30			5.00					X		X	I		X						INSTALL NEW SIGN AND POST NEXT TO BOX# 2683	X				
SB	MM 2.984, LT	F	R2-1	24	30			5.00					X		X	I		X						INSTALL NEW SIGN AND POST AT BOX# 2881	X				
NB	MM 3.193, RT	A	R2-1	24	30			5.00					X		X	I		X						INSTALL NEW SIGN AND POST 770 FT NORTH OF THE CENTER OF HILLVIEW RD	X				
SB	MM 3.277, LT	F	WI0-IL	36	36			9.00					X		X	2		X						INSTALL NEW CURVE/INTERSECTION SIGN ON 2-POSTS 315 FT NORTH OF THE CENTER OF HILLVIEW RD	X				
		F	W16-8P	30	8			1.67																INSTALL BENEATH THE CURVE/INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT		10			
SB	MM 3.304, LT	F E	WI-8 L WI-8 R	18 18	24 24		  	3.00 3.00								I		X						INSTALL NEW CHEVRONS BACK-TO-BACK ON A SIGN BRACKET ON A SINGLE POST SPACED AT 120 FT APART GOING SOUTH. INSTALL THE FIRST ASSEMBLY 120 FT NORTH OF POLE# 77/755	X X				
SB	MM 3.327, LT	F E	WI-8 L WI-8 R	18 18	24 24		  	3.00 3.00								I		X						INSTALL NEW CHEVRONS BACK-TO-BACK ON A SIGN BRACKET ON A SINGLE POST ADJACENT TO POLE# 77/755	X X				
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".										EA	EA	EA	EA 7	EA	EA 7		FT 40	FT 180	FT 0		LB	LB	LB	LB	PROJECT NAME: STATEWIDE NORTHWEST REGION PROJECT NUMBER: STP HRRR(5)				
							SHEET SUBTOTALS	SF 75.83	SF	EA 7				EA 7	EA 7		FT 220		EA	LB			FILE NAME: I0K018_wrk.dgn PROJECT LEADER: JLS DESIGNED BY: NLA RICHMOND TRAFFIC SIGN SUMMARY SHEET 7			PLOT DATE: 17-SEP-2012 11:33 DRAWN BY: ITS CHECKED BY: JLS SHEET 36 OF 51			