STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - NORWICH 2 (BEAVER MEADOW ROAD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 4.894, RT	A	W7-1B	30	30		8%	6.25					X		X	1		X								INSTALL NEW SIGN AND POST 132 FT SOUTH OF POLE# 52/186/6T/562/5	X		
		A	W7-2BP	24	18		TRUCKS USE LOWER GEAR	3.00																		INSTALL NEW SIGN BENEATH PERCENT GRADE HILL SYMBOL WARNING SIGN AT CORRECT SIGN HEIGHT	X		
NB	MM 4.928, RT	A	TOWN SIGN	30	30		BLIND DRIVE						X		X											REMOVE SIGN AND POST	X		
NB	MM 4.942, RT	A	W1-4Ma L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 120 ~~48~~ FT NORTH OF POLE# 52/186/6T/562/5		9	
		A	W16-8P	36	8		Chapel Hill Rd	2.00																		INSTALL NEW SIGN BENEATH MODIFIED LEFT REVESE CURVE WARNING SIGN AT THE CORRECT SIGN HEIGHT		9	
NB	MM 4.954, RT	A	S3-1	30 36	30 36	F-Y-G F-Y-G	SCHOOL BUS STOP AHEAD NEW INTERNATIONALLY RECOGNIZED SIGN S3-1 INSTALLED	6.25 9.00					X		X	1 2		X		AFTER INSTALLATION OF THE TEXT SIGN, THE PROJECT MANAGER REQUESTED THE SYMBOL SIGN BE INSTALLED.						INSTALL NEW SIGN AND POST 185 FT NORTH OF POLE# 52/186/6T/562/5	X		
NB	MM ~~4.980~~ 4.975, RT	B	W1-8 R	18	24			3.00								1		X								INSTALL NEW SIGN AND POST 34 ~~69~~ FT SOUTH OF POLE# 4	X		
NB	MM 4.997, RT	A	W1-6 L	48	24								X		X X											REMOVE SIGN AND POSTS			
		A B	LW1-8 L W1-8 R	18 18	24 24		B-B	3.00 3.00								~~1~~ 2		X								SEPARATE POSTS INSTALL BACK-TO-BACK ON ~~A SIGN BRACKET AND A SINGLE POST~~ 121 FT NORTH OF POLE# 4	X X		
NB	MM 5.007, RT	A B	W1-8 L W1-8 R	18 18	24 24		B-B	3.00 3.00								~~1~~ 2		X								SEPARATE POSTS INSTALL BACK-TO-BACK ON ~~A SIGN BRACKET AND A SINGLE POST~~ 211 FT NORTH OF POLE# 4	X X		
NB	MM 5.024, RT	A B	W1-8 L W1-8 R	18 18	24 24		B-B	3.00 3.00								~~1~~ 2		X								SEPARATE POSTS INSTALL BACK-TO-BACK ON ~~A SIGN BRACKET AND A SINGLE POST~~ 301 FT NORTH OF POLE# 4	X X		
SB	MM 5.040, LT	F	TOWN SIGN	30	30		BLIND DRIVE						X		X											REMOVE SIGN AND POST	X		
		F	W1-4Md L	30	30		HIDDEN DRIVE LEFT	6.25								1		X								INSTALL NEW SIGN AND POST 132 FT SOUTH OF AND ACROSS FROM POLE# NET/52/88/562/2		9	
SB	MM ~~5.048~~ 5.053, LT	F E	W1-8 L W1-8 R	18 18	24 24		B-B	3.00 3.00								~~1~~ 2		X								SEPARATE POSTS INSTALL BACK-TO-BACK ON ~~A SIGN BRACKET AND A SINGLE POST~~ ~~90~~ 65 FT SOUTH OF AND ACROSS FROM POLE# NET/52/88/562/2	X X		
							SHEET SUBTOTALS	SF ~~57.00~~ 66.00	SF	EA 5				EA 6		EA ~~9~~ 15		FT 135		EA	LB								
										EA 5	EA	EA	EA	EA 6	EA		FT	FT 135	FT		LB	LB	LB	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(6)

FILE NAME: 10k020_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
NORWICH 2 TRAFFIC SIGN SUMMARY 1

PLOT DATE: 04-JUN-2010
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 26 OF 44