STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - CAMBRIDGE

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS FT'B FT	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM, 1.677, LT	F	W1-2R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST AT EAST AND ACROSS FROM EAST END OF ELECTRIC FENCE GATE	X		
EB	MM, 1.885, RT	A	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1		X								REPLACE EXISTING SIGN 560 FT WEST AND ACROSS FROM POLE #12A/18	X		
EB	MM, 1.885, RT	A	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1		X								REPLACE EXISTING SIGN 285 FT WEST OF POLE #12A/18	X		
EB	MM 2.000, RT TO MM 2.119, RT	A B		6	8		(10) TYPE II - 6" X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (10) BACK-TO-BACK 60 FT APART ON 5 POSTS. INSTALL FIRST DELINEATOR 48 FT EAST AND ACROSS FROM POLE #12A/18		7	
EB	MM 2.166, RT TO MM 2.230, RT	A B		6	8		(6) TYPE II - 6" X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (6) BACK-TO-BACK 60 FT APART ON 3 POSTS. INSTALL FIRST DELINEATOR 95 FT EAST AND ACROSS FROM POLE #12A/15		7	
WB	MM, 2.250, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00								1		X								INSTALL NEW SIGN AND POST 20 FT WEST OF TOWN LINE	X		
										EA	EA	EA	EA	EA	EA		FT	FT	FT		LB	LB	LB	LB					
													2		2			60											
							SHEET SUBTOTALS	SF 21.25	SF	EA 2				EA 2		EA 4	FT 60			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: d10k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
CAMBRIDGE TRAFFIC SIGN SUMMARY 3

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 19 OF 54