

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS			EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL 0/(in)				SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL				
				WIDTH	HEIGHT			“A”	“B”	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN		REMOVE	1.75	2.00	2.50	FOUNDATION	3.00	3.50			4.00	5.00	DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
																								DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER			

							SANDY BIRCH ROAD																								
WB	MM 0.010 LT	F	R1-1	30	30			6.25					X		X	1		15										REPLACE EXISTING STOP SIGN AND POST LOCATED 111' EAST OF AND ACROSS FROM POLE # R1-13/39/9431/1	X		
WB	MM 0.010 LT	H G	D3-1	60	12			5.00								2		30										REPLACE THE EXISTING STREET NAME SIGN ON TWO NEW POSTS LOCATED 111' EAST OF AND ACROSS FROM POLE # R1-13/39/9431/1		15	
EB	MM 0.019 RT	A	R2-1	24	30			5.00								1		15										INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 63' EAST OF POLE # R1-13/39/9431/1	X		
WB	MM 0.074 LT	F	W3-1	30	30			6.25								1		15										INSTALL A NEW STOP AHEAD SIGN AND POST LOCATED 277' WEST OF AND ACROSS FROM POLE # R1-13/39/9431/1	X		
EB	MM 0.074 RT	A	R2-1	24	30								X		X													REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 277' WEST OF POLE # R1-13/39/9431/1			
							FONTAINE DRIVE 1																								
WB	MM 0.007 LT	F	R1-1	30	30			6.25					X		X	1		15										REPLACE EXISTING STOP SIGN AND POST LOCATED ADJACENT TO POLE # 40T/4	X		
WB	MM 0.007 LT	H G	D3-1	42	12			3.50					X															REPLACE THE EXISTING STREET NAME SIGN ABOVE THE NEW R1-1 SIGN LOCATED ADJACENT TO POLE # 40T/4		14	
EB	MM 0.019 RT	A	R2-5	24	30								X		X													REMOVE EXISTING REDUCED SPEED AHEAD SIGN AND POST LOCATED 190' WEST OF POLE # 4-1/NET/37A			
EB	MM 0.019 RT	A	R2-1	24	30			5.00								1		15										INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 190' WEST OF POLE # 4-1/NET/37A	X		
EB	MM 0.052 RT	A	R2-1	24	30								X		X													REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 16' WEST OF POLE # 4-1/NET/37A			
							FONTAINE DRIVE 2																								
WB	MM 0.006 LT	F	R1-1	30	30			6.25					X		X	1		15										REPLACE EXISTING STOP SIGN AND POST LOCATED 32' EAST OF THE INTERSECTION OF BALLARD ROAD	X		
WB	MM 0.006 LT	H G	D3-1	42	12			3.50																				INSTALL A NEW STREET NAME SIGN ABOVE THE NEW R1-1 SIGN LOCATED 32' EAST OF THE INTERSECTION OF BALLARD ROAD		14	

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

SF 47.00

SF

EA 7

EA 6

EA 8

FT 120

EA

LB

PROJECT NAME: STATEWIDE NORTHWEST REGION

PROJECT NUMBER: STP HRRR(17)

FILE NAME: georgiatrafficsign6.dgn

PROJECT LEADER: J. DEVLIN

DESIGNED BY: N. PATTIS

GEORGIA TRAFFIC SIGN SUMMARY SHEET 6

PLOT DATE: 1/22/2014

DRAWN BY: N. PATTIS

CHECKED BY: B. GROSE

SHEET 31 OF 73