

BRIDGE RAILING, H.D. STEEL BEAM, TYPE D
T.H.57 STA. 10+33 TO STA. 10+83 RT. & LT.

GUARD RAIL, H.D. STEEL BEAM WITH WOOD POST,
TYPE II (A588 STEEL) (6'-3" POST SPACING TYPICAL)

Vt. II STA. 4+39 RT. TO T.H.57 STA. 10+33 RT.
T.H.57 STA. 10+33 LT. TO Vt. II STA. 5+35 RT.
T.H.57 STA. 10+83 TO STA. 11+08 RT. & LT.

BREAKAWAY CABLE TERMINAL FOR GUARD RAIL,
STEEL BEAM W/ WOOD POSTS, TYPE II

Vt. II STA. 4+39 RT.
Vt. II STA. 5+37 RT.

ANCHOR FOR STEEL BEAM GUARD RAIL
WITH STEEL OR WOOD POST AT OPENINGS
T.H. 57 STA. 11+00 RT. & LT.

STONE FILL, TYPE II
CHAN. STA. 4+72 TO 5+25 RT.

TEMPORARY BRIDGE NOTES:

- 1) TEMPORARY BRIDGE IS TO BE LOCATED IN APPROXIMATE LOCATION AS PREVIOUS TEMPORARY CROSSINGS AND APPROXIMATELY AS SHOWN ON THIS DRAWING.
- 2) EVERY EFFORT SHALL BE MADE TO SAVE AS MANY TREES AS POSSIBLE.
- 3) FINAL LOCATION OF TEMPORARY BRIDGE, ACCESS ROAD, AND CONSTR. EASEMENTS SHALL MEET THE APPROVAL OF THE PROPERTY OWNER.

Vt. TEL. CO.
87-1
95-1

END SIDELINE, STA. 6+00
CONSTRUCT SATISFACTORY APPROACH

STOP ROADWAY
BEGIN BRIDGE
STA. 10+35.00
F.G. EL. 501.85

BEGIN PROJECT
M/L 10+00.00 = CHAN. 5+00.00
 $\Delta = 90^\circ 19' 15''$ LT.

BEGIN SIDELINE, STA. 4+00
CONSTRUCT SATISFACTORY APPROACH

END PROJECT, STA. 12+00
CONSTRUCT SATISFACTORY APPROACH

END BRIDGE
RESUME ROADWAY
STA. 10+81.00
F.G. EL. 500.91

T.B.M. #1
TOP OF CONC.
LT. & RT. ABUT. #1
ASSMD. ELEV.
500.00

T.B.M. #2
S.I.R. 12' ELM
ASSMD. ELEV.
503.10

STONE FILL, TYPE II
(TIP)

3 LARGE ROCKS, APPROX. 1 CY. EACH
PLACE AS SHOWN IN TRIANGULAR GROUP,
TO BE PAID FOR AT THE UNIT PRICE BID
FOR STONE FILL, TYPE II

P.O.T. 11+00.00

0 10 20 40
SCALE IN FEET

SURVEYED BY TESSIER DATE 12/79
DRAWN BY ORVIS DATE 2/80
TRACED BY PASE DATE 2/80
CHESTER
PROJ. NO. BRZ. 1442(2)
SHEET 6 OF 32