

PLAN	DATE	DEC 11/68
	BY	CHAS. BRUNING
	SURVEYED	NO
	NOTED	NO

PROFILE	DATE	DEC 11/68
	BY	CHAS. BRUNING
	SURVEYED	NO
	NOTED	NO

EXISTING UNDERGROUND TELEPHONE/UTILITIES WITHIN THE CONSTRUCTION LIMITS TO BE RELOCATED BY OTHERS.

PI. 127+11.70 = 127+10.73

Curve #3
 $\Delta = 3^{\circ}18'41''$
 $D = 1^{\circ}30'$
 $R = 3819.72$
 $T = 277.15$
 $L = 553.33$
 $E = 10.04$
 Bank 0.021 ft/ft

RELOCATE MAILBOX, SINGLE SUPPORT TEMPORARY 4" YELLOW LINE
 133+48 LT (SEE STANDARD TURNOUT DETAIL SHEET 3b)

CONSTRUCT DRIVE
 LT
 129+68 15' WIDE (GRAVEL)
 131+75 40' WIDE (GRAVEL)
 134+00 40' WIDE (GRAVEL)
 131+50 RT 12' WIDE (GRAVEL)
 132+71 25' WIDE (GRAVEL)
 135+00 12' WIDE (GRAVEL)
 140+88 16' WIDE (GRAVEL)

DURABLE 4" WHITE LINE
 126+00 (11' LT) - 142+00 (11' LT)
 126+00 (11' RT) - 142+00 (11' RT)

SPECIAL DITCH (ITEM 208.15)
 LT 127+00 ~ 128+68
 RT 139+50 ~ 140+50

STONE FILL, TYPE I

LT 137+75 ~ 140+50
 128+00 ~ 129+50
 129+00 ~ 131+20
 131+00 ~ 132+50
 132+00 ~ 134+72
 135+00 ~ 136+05
 140+15 ~ 142+00
 SPRING

EROSION MATTING

LT 126+00 ~ 128+68

DURABLE 4" YELLOW LINE
 126+00 ~ 142+00, E, DBL.

CONSTRUCT EARTH BERM

RT 136+05 ~ 136+50

