

2' Bit Conc. Pav't

SECTION C-C

3' Cedar (Save)  
34+15  
Rev 34+10 Lt  
Construct Paved Walk (3' Wide)  
To Be Paid as Bit Conc.  
Sidewalk

3' Cedar (Save)  
34+06

2' Cedar  
33+82.5

Rev. 34+00 Lt  
End New 6"x54" Underdrain  
w/ F.B @ 34+00 Lt.

18" M (Save)  
33+91

I.P.  
33+73.5

+64  
1' Bush (Save)

33+60  
1' BUSH (Save)

ESM

ESM

6" Plastic Assumed Loc.

34+09

34+00

33+64

Ray B  
701.95

Rev. 33+99.38

C=136 (127)  
F=21

+83.5  
2' Bush (Remove)

+83.5  
Lilac (Save)

PLANES V.R.N. 2/21/93

Width Varies 16'-24'

Section B-B  
@ 33+93 Rt  
Scale: 1"=5'

700

Rev. 33+93 Rt  
Construct Drive  
24' Wide (Paved)

695

Rev. 33+84 Rt  
End Vertical Granite Curb

Rev. 33+71 Rt  
Begin Vertical Granite Curb

Rev. 33+64 Rt  
Construct Drive  
16' Wide (Paved)

695

Rev. 33+55 Rt  
End Vertical Granite Curb

Notes: The Contract is to install a 4' picket fence along the top of the front yard bank from 34+00 Rt ~ 34+82 Rt. Costs for this work and associated materials will be paid under Item 620.11 (M.O.D.)

34+11 Rt  
Begin Vertical Granite Curb

Section A-A  
12" Subbase  
8 Feet  
8 Feet  
2" Bituminous Conc. Pav't