

Note: The two stone walls located between Sta. 48+45 RT± and Sta. 49+45 RT± which will be removed during the Construction period are to be reset as follows: The section presently located between 49+27 RT± and 49+45 RT± will be relocated at approximately the same stations on the westerly edge of the new drive at 49+60 RT±. The section presently located between sta. 48+45 RT± and 49+00 RT± will be relocated westerly of the construction limits, between the same stations. Payment for removing and resetting the wall will be under item 602.20, Dry Rubble Masonry, and shall be Non-Gov't. Participating.

